

ANALYZING THE EFFECTS OF WALKWAY ATTACHMENTS ON HIGHWAY CANTILEVERED OVERHEAD SIGN STRUCTURES

by

HUNTER SENIOR – hunter.senior@ku.edu

Dr. Caroline Bennett, Ph.D., P.E. – crb@ku.edu

Dr. William Collins, Ph.D., P.E. – william.collins@ku.edu

Dr. Jian Li, Ph.D., P.E. – jianli@ku.edu

Dr. Mark Ewing, Ph.D. – mewing@ku.edu

LAWRENCE, KANSAS

Date Submitted: May 17th, 2019

The thesis committee for Hunter Senior
certifies that this is the approved version of the following thesis:

**ANALYZING THE EFFECTS OF WALKWAY ATTACHMENTS ON
HIGHWAY CANTILEVERED OVERHEAD SIGN STRUCTURES**

Chair: Dr. Caroline Bennett, Ph.D., P.E.

Dr. William Collins, Ph.D., P.E.

Dr. Jian Li, Ph.D., P.E.

Dr. Mark Ewing, Ph.D.

Date Approved: May 17th, 2019

ABSTRACT

Cantilevered overhead sign structures (COSS) experience cyclic loading due to stochastic loads such as natural wind gusts (NWG). These wind loads cause large deflections in the cantilever and excessive stresses can develop at the connection between the cantilever and mast where fatigue performance is a concern. Modifications to the sign structures pose further concerns as changes to the aerodynamic properties could have unintended consequences. A design consideration of COSS is serviceability of the sign through the use of a steel grate walkway that workers can use for maintenance on the sign. The steel grate walkways on COSS are rarely used for maintenance anymore, hence are being removed by multiple state DOTs to prevent vandalism. However, the impact on COSS with the removal of the walkways is unknown.

The research described analyzes the effect the walkways have on the dynamic and aerodynamic properties of COSS. Computer simulations of 32 different COSS configurations were carried out to see the effect of the grate removal on the natural frequency and the mass of the system. Aerodynamic performance is considered through the use of computational fluid dynamics (CFD) and experimental testing where the wind pressure on the sign in both axial directions and effects of vortex shedding are examined. Findings made by the research include: 1) the walkway has a minimal effect on the system's mass and natural frequencies, 2) the walkway has minimal effect on the wind-induced force on the sign, 3) vortex shedding is not exacerbated with removal of a walkway attachment, and 4) walkway removal does not change the fatigue performance of the connection between the cantilever and mast. Based on these findings, the removal of walkways is not problematic for COSS.

TABLE OF CONTENTS

| | |
|---|-----|
| ABSTRACT | iii |
| NOTATION | iv |
| ACKNOWLEDGEMENTS | vii |
| CHAPTER 1 - INTRODUCTION AND BACKGROUND | 1 |
| 1.1 Background | 1 |
| 1.2 Problem Statement | 4 |
| 1.3 Research Objectives | 4 |
| 1.4 Thesis Organization | 6 |
| 1.5 Literature Review | 6 |
| 1.5.1 – <i>Damage Reporting</i> : | 6 |
| 1.5.2 – <i>Fatigue</i> : | 10 |
| 1.5.3 – <i>Dynamic Properties</i> : | 12 |
| 1.5.4 – <i>Vortex Shedding</i> : | 13 |
| CHAPTER 2 – METHODS | 16 |
| 2.1 Design Envelope and Model Selection | 16 |
| 2.2 Characteristic Mode Shapes | 20 |
| 2.3 Finite Element Modeling – Fundamental Frequencies | 22 |
| 2.3.1 – <i>Part and Assembly Creation and Meshing</i> : | 22 |
| 2.3.2 – <i>Material Definition</i> : | 24 |
| 2.3.3 – <i>Connections and Boundary Conditions</i> : | 25 |
| 2.3.4 – <i>Step Creation</i> : | 26 |
| 2.4 Loading Methodology | 26 |

| | |
|---|----|
| 2.4.1 – <i>Design Loads and Wind Speed Selection:</i> | 28 |
| 2.5 Computational Fluid Dynamics (CFD) Modeling | 30 |
| 2.5.1 – <i>Defining CFD Interaction Surfaces and Material Definition:</i> | 31 |
| 2.5.2 – <i>Part and Assembly Creation, and Boundary Condition Selection:</i> | 33 |
| 2.5.3 – <i>Fluid Domain Meshing:</i> | 37 |
| 2.5.4 – <i>Step Creation and Turbulence Modeling Parameters:</i> | 39 |
| 2.6 Finite Element Modeling – Dynamic Loading..... | 42 |
| 2.6.1 – <i>Step Creation and Load Application:</i> | 42 |
| 2.7 Experimental Methods | 43 |
| 2.7.1 – <i>Scale Model Construction:</i> | 44 |
| 2.7.2 – <i>Experimental Setup:</i> | 47 |
| CHAPTER 3 – RESULTS | 51 |
| 3.1 Finite Element Modeling – Fundamental Frequencies of the COSS | 51 |
| 3.2 Computation Fluid Dynamic Modeling Results | 55 |
| 3.3 Finite Element Modeling – Dynamic Loading..... | 65 |
| 3.4 Experimental Results..... | 70 |
| CHAPTER 4 – CONCLUSIONS AND RECOMMENDATIONS | 75 |
| 4.1 Conclusions Regarding Changes to Dynamic Properties with Walkway Removal..... | 75 |
| 4.2 Conclusions Regarding Changes to Aerodynamic Shape and Loading Conditions | 76 |
| 4.3 Future Work | 77 |
| REFERENCES | 78 |
| APPENDIX A1 | 83 |
| A1.1 – Y-Component of Velocity Behind Large Sign at V=30 mph (13.4 m/s) | 83 |

| | |
|--|-----|
| A1.2 – Y-Component of Velocity Behind Large Sign at V=61.2 mph (27.4 m/s) | 87 |
| A1.3 – Y-Component of Velocity Behind Large Sign at V=105mph (46.9 m/s) | 91 |
| A1.4 – Y-Component of Velocity Behind Medium Sign at V=30 mph (13.4 m/s) | 95 |
| A1.5 – Y-Component of Velocity Behind Medium Sign at V=61.2 mph (27.4 m/s) | 99 |
| A1.6 – Y-Component of Velocity Behind Medium Sign at V=105mph (46.9 m/s) | 103 |
| A1.7 – Y-Component of Velocity Behind Small Sign at V=30 mph (13.4 m/s) | 107 |
| A1.8 – Y-Component of Velocity Behind Small Sign at V=61.2 mph (27.4 m/s) | 111 |
| A1.9 – Y-Component of Velocity Behind Small Sign at V=105mph (46.9 m/s) | 115 |
| APPENDIX A2 | 119 |
| A2.1 – Large Sign Velocity Profile at V=30 mph (13.4 m/s) | 119 |
| A2.2 – Large Sign Velocity Profile at V=61.2 mph (27.4 m/s) | 120 |
| A2.3 – Large Sign Velocity Profile at V=105mph (46.9 m/s) | 122 |
| A2.4 – Medium Sign Velocity Profile at V=30 mph (13.4 m/s) | 123 |
| A2.5 – Medium Sign Velocity Profile at V=61.2 mph (27.4 m/s) | 125 |
| A2.6 – Medium Sign Velocity Profile at V=105mph (46.9 m/s) | 126 |
| A2.7 – Small Sign Velocity Profile at V=30 mph (13.4 m/s) | 127 |
| A2.8 – Small Sign Velocity Profile at V=61.2 mph (27.4 m/s) | 129 |
| A2.9 – Small Sign Velocity Profile at V=105mph (46.9 m/s) | 130 |
| APPENDIX A3 | 132 |
| Appendix B | 144 |

ACKNOWLEDGEMENTS

This project would not have been possible without support and funding from the Kansas Department of Transportation. Thank you for making this research possible.

I am greatly indebted to Dr. Caroline Bennett for picking me up as a student and for her guidance on this project. She personally saved my research and my degree, and I would like to thank her for all her time and effort. Thank you to Dr. William Collins for his support on the experimental testing. Both Dr. Bennett and Dr. Collins provided impeccable leadership, critical feedback, and endless encouragement which was vital to my degree and will serve me well in my career.

I am eternally grateful to Dr. Mark Ewing and Dr. Jian Li for serving on the defense committee and for their important inputs that kept this project moving forward.

I must also thank the help and contributions provided by Dr. Rémy Lequesne, Dr. Matt O'Reilly, and Dr. Joshua Roundy for providing crucial tools for my research.

I am thankful for the lab techs Kent Dye, David Woody, and Josh Ostermann. They constantly took time out of their busy schedules to help and teach me. Their support was essential to this project.

Thank you to the Aerospace Department for allowing me to use the wind tunnel, with special thanks to Wes Ellison and Grant Godfrey for all of the hours they put in to this project.

I would also like to thank my fellow engineering grad students for creating such a helpful and inviting community, especially Duncan MacLachlan for taking the time to teach me Abaqus and answering all of my questions.

Lastly, on a more personal note, I would like to acknowledge the selfless donations of Karen Papi, Jeff Meyer, and Luis Arroyo to my family, and I would like to express my sincerest gratitude to my friends and family for their ever-loving support and encouragement, with special thanks to Emily Draeger for standing by me, and for everything she has done.

CHAPTER 1 - INTRODUCTION AND BACKGROUND

1.1 Background

Cantilevered overhead sign structures (COSS) are ubiquitous in highway infrastructure across the United States. COSS are used to convey information to traveling motorists in an efficient and effective manner. However, fatigue cracks have been discovered in COSS connections over the past few decades, limiting the service lives of these structures, and sometimes even resulting in complete failures. Because of such incidences, highway sign structures have received increasing attention surrounding fatigue performance and design over the past two decades, with fatigue design provisions first being included in the American Association of State Highway Transportation Officials (AASHTO) Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals (SLTS) in 2001.

There are four popular construction types for COSS: 1) monotube, 2) two-chord truss, 3) three-chord truss, and 4) four-chord truss, all of which are shown in Figure 1.1.1. These have the same function and general shape, but different assemblies. The construction type is generally uniform within a state, but varies state to state.


COSS only require one support which reduces materials, earthwork, labor costs, and road closures; thus, COSS can be a more attractive option to state DOTs when compared to a full-span overhead sign structure. Additionally, using a single support reduces the number of hazards a motorist can face in the event of an accident (Dexter and Ricker 2002).



(a)



(b)



(c)



(d)

Figure 1.1.1 – Popular COSS Construction Types: (a) monotube, (b) two-chord truss; (c) three-chord truss; and (d) four-chord truss

COSS can experience high wind fluctuations from natural wind gusts. Natural wind produces a significant load on COSS because the aluminum signs create a large shape that catches the wind. This wind loading can displace the COSS both vertically and horizontally, and deflections can be quite substantial at the end of the cantilever. COSS undergo significant cyclical loading in their lifetime due to wind loads, and experience substantial deflections in the mast truss. Because of this, COSS are now designed with fatigue as a consideration.

Over the past three decades, a number of fatigue related failures have been observed in COSS (Dexter and Ricker 2002). Specifically, two-chord COSS experienced the highest number of fatigue failures due to the dynamic response of natural wind gusts and susceptibility to vortex shedding (Gallow et al. 2015). Additionally, defective welds have been observed in two-chord COSS. Such fabrication-related issues have resulted in the prevalence of crack development and crack propagation in the connection between the mast truss and pole, called the “box connection”. Figure 1.1.2 shows where state DOTs have been monitoring crack growth in a box connection through discrete visual inspections. (Although the cracks are not visible in the figure, marks indicating their growth are shown.)



Figure 1.1.2 – Typical crack monitoring at the box connection

To accommodate maintenance of the signage and structure, COSS often include a steel grate walkway in front of the sign, as shown in Figure 1.1.3 and Figure 1.1.4. The walkway usually spans the whole length of the sign and is typically made of steel grating supported on L-shaped hanger supports suspended from the bottom chord. On occasion, the walkway attachment is removed to reduce incidences of vandalism. The influence of walkway removal on the dynamic properties of the structures and the aerodynamic shape of the sign is unknown. It is possible that removal of the walkway could result in worsened fatigue performance of COSS.



Figure 1.1.3 – Steel grate walkway on a two-chord COSS



Figure 1.1.4 - Steel grate walkway on a two-chord COSS

1.2 Problem Statement

While intended to be a component for serviceability, the steel grate walkway can be a liability for overhead sign structures (OSS). Vandals have been able to use walkways to deface signs. To combat this, multiple state DOTs have removed walkways from OSS. Additionally, state DOTs tend to use bucket trucks for most maintenance on OSS, rendering the walkway attachment somewhat unnecessary.

It is not evident what impact walkway removal has on the structural performance of COSS. Two important structural characteristics are changed when the attachment is removed: 1) dynamic properties of the COSS and 2) aerodynamic shape of the COSS. It is conceivable that such changes may have significant effects on the fatigue performance of COSS. It is unclear how removing the walkway attachment may affect the fatigue performance of two-chord COSS.

At first consideration, it may seem that removing mass at the end of a cantilever would help improve fatigue performance of the structure by reducing natural frequencies, but it is possible that other effects may have negative influence on fatigue performance. The removal of mass could cause two-chord COSS to experience more fatigue cycles (Craig and Kurdila 2006). The walkway attachment could deflect wind gusts away from the sign, resulting in larger stress demands when removed. The walkway could act as a diffuser to disrupt eddy interaction which leads to vortex shedding. In other words, the steel grate walkway may be an unintended but important piece for satisfactory fatigue performance.

1.3 Research Objectives

The aim of the research presented in this thesis is to characterize how the removal of walkway attachments affects the dynamic properties and aerodynamic shape of two-chord COSS

used in the Kansas Department of Transportation highway inventory. This was achieved by using analytical and experimental techniques, specifically:

- 1) ***Dimensional analysis of two-chord COSS*** – to capture a range of realistic design characteristics and to produce a diverse group of two-chord COSS for subsequent analytical modeling.
- 2) ***Modal response definition*** – to characterize how two-chord COSS react under natural wind gusts and certain aeroelastic phenomena, such as vortex shedding.
- 3) ***Fundamental frequency calculation*** – to calculate changes in the dynamic response for COSS with and without the walkway attachment.
- 4) ***Computation fluid dynamic (CFD) modeling*** – to characterize how the aerodynamic shape of the sign varies depending on the presence of the walkway, considered by computing pressures on the sign shape, observing how wind flows around the sign shape, and observing how eddies and vortices form and interact in the wake of the sign shape.
- 5) ***Experimental verification*** – to validate results obtained from the CFD modeling through use of a wind tunnel.
- 6) ***Dynamic loading*** – to characterize how COSS respond to natural wind using loading data obtained from the CFD modeling.

By using this approach, conclusions can be drawn on the influence of the walkway attachment on the fatigue performance of two-chord COSS.

It is important to note that truck-induced wind gusts (TIWG) were not investigated in this research. TIWG result in considerably lower wind gusts when compared to natural wind gusts (Creamer et al. 1979). Also, the walkway attachment is the most influential area affected by TIWG. Without the attachment, TIWG would have negligible area to project onto resulting in negligible

force. Additionally, modeling cyclical loading from TIWG is not specified in any AASHTO Specification; therefore, conclusions could not be formulated for fatigue life regarding TIWG.

1.4 Thesis Organization

Section 1.5 presents a literature review of pertinent studies and findings on current problems affecting COSS. The literature review also provides background information on the basis of the methodology used in this research. Chapter 2 describes how the research was conducted. Both analytical modeling techniques and experimental methods are addressed. Chapter 3 outlines the results of both the analytical modeling and experimental testing. Chapter 4 summarizes the results and formulates conclusions. Chapter 4 also includes recommendations for future work around fatigue performance of COSS. The Appendix provides construction documentation and additional results from the analytical modeling that was used to form conclusions.

1.5 Literature Review

This section serves as background and context regarding performance problems encountered with COSS, and outlines topics used as baseline assumptions in modeling techniques summarized in Chapter 2.

1.5.1 – Damage Reporting:

NCHRP Report 412 (Kaczinski et al. 1998):

The National Cooperative Highway Research Program (NCHRP) Report 412 (Kaczinski et al. 1998) describes the first phase of NCHRP Project 10-38, which aimed to improve the performance of COSS by mitigating fatigue, improving established design criteria, and investigating how COSS are failing across the United States. Four wind loading categories were identified as

likely sources for large-amplitude vibrations, which when paired with natural frequencies of COSS, could lead to fatigue failures. The four categories were: 1) natural wind gusts, 2) truck-induced wind gusts, 3) galloping, and 4) vortex shedding. Revisions to the AASHTO Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals were recommended.

NCHRP Report 412 included descriptions of the characteristics of natural wind gusts and how they affect COSS. Natural wind gusts have a variability in velocity and direction of air flow, and are characterized by a spectrum of fluctuating velocity components over a given plane projected onto a structure. The fluctuating pressure inherent to natural wind gusts induces vibrations onto a structure. Kaczinski et al. (1998) claimed that variations in velocity fluctuations associated with natural wind gusts typically increase between 5 percent and 25 percent with intense gusts. The subsequent AASHTO SLTS (AASHTO 2001) compensates for this by applying a gust factor of at least 1.14 to the design load, increasing for structures that require it. A case is made that this factor is adequate for ultimate strength design of COSS, because state DOTs have “no reported failures directly attributed to the exceedance of the ultimate strength of cantilevered support structures due to extreme gust loading conditions” (Kaczinski et al. 1998). The authors showed that natural wind gusts are purely *aerodynamic* and not *aeroelastic* like galloping and vortex shedding. Therefore, “stiffening the structure or adding mass does not reduce the loading effect as it does for aeroelastic phenomena” (Kaczinski et al. 1998). The authors also claimed that “changing the natural frequency through changes of mass and/or stiffness does not reduce the load effect significantly...” (Kaczinski et al. 1998). This suggests that the variances in shape and mass across structures have little effect on natural wind gusts.

A goal of NCHRP 10-38 was to categorize fatigue-critical connections in sign structures to provide an ability to better estimate remaining service life. Connections considered were: 1) the base of the supporting pole to the anchor bolts and 2) the connections between the supporting pole and the mast truss, which vary by construction style. The connections were categorized with respect to the AASHTO fatigue design curves shown in Figure 1.5.2 (AASHTO 2015b). The majority of connections between the supporting pole and the mast truss were classified as E or E' connections, indicating very poor fatigue performance.

Evidence was presented that all COSS designed using the 1994 AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaries, and Traffic Signals need to be reevaluated. In fact, 36 DOTs reported that they experienced fatigue problems with wind-induced vibration of COSS. Generally, the reported vibrations were observed to occur in the plane of the structure, activated by aeroelastic phenomena. The subsequent AASHTO SLTS (AASHTO 2001) compensates for this by applying a vertical 21 psf (1005 Pa) pressure to all horizontal areas of the sign structures for sufficient strength for galloping.

NCHRP Report 494 (Fouad, et al. 2003):

Work described in NCHRP Report 494 (NCHRP Project 17-10(2), Fouad, et al. 2003) was a continuation of the work begun under NCHRP Project 10-38, extending the research to non-cantilevered signs structures, which have also exhibited fatigue problems. Eight state DOTs reported problems with OSS. Fouad, et al. (2003) made the case that COSS and OSS fatigue problems stemmed from the same wind induced vibration. This resulted in the creation of new fatigue criteria that would change the existing loading recommendation. As in the work done under NCHRP 10-38, the four categories responsible for wind induced vibration were 1) natural wind

gusts, 2) TIWG, 3) galloping, and 4) vortex shedding. The loading recommendations are as follows, where the values are applied to all horizontal areas of all OSS:

- 1) Natural wind gusts – 5.2 psf (250 Pa).
- 2) TIWG – 10.2 psf (490 Pa), recommendation also provides a 7.5 psf (360 Pa) horizontal load to vertical faces, but this is dramatically less than natural wind gusts.
- 3) Galloping – 21 psf (1000 Pa), can be ignored for non-cantilevered structures.
- 4) Vortex Shedding – may be disregarded as long as “...sign blanks are used during the construction...” (Fouad et al. 2003). This is to prevent exposed shapes that are susceptible to eddy interaction at critical points in the span of the sign structures.

These loading recommendations were adapted in the successive AASHTO Specifications (AASHTO 2009). Despite the research conducted in the report, it is still unclear whether or not fatigue failures in COSS and OSS are primarily induced by large-magnitude loads produced by galloping and vortex shedding, or if the problems primarily stemmed from fabrication errors. The authors concluded that additional testing, inspections, and data collection is required before definitive conclusions can be drawn.

The authors recommended using additional gusset plates or thicker steel plates in the connections between the supporting pole and the mast truss (typical connection shown in Figure 1.1.2), to increase the stiffness of the structure and provide additional moment capacity at the connection.

AASHTO LRFD Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2015 First Edition (AASHTO 2015a):

Section 11 of the AASHTO LRFD SLTS Specification outlines the requirements and recommendations provided in NCHRP Reports 412 (Kaczinski et al. 1998) and 494 (Fouad et al. 2003) for adequate fatigue design. The updated loads for application on horizontal areas are found in this section. The section also recommends the design of infinite service life connections for both connections identified in NCHRP Report 412 (Kaczinski et al. 1998). This is done by modeling them with constant amplitude fatigue life which is shown in Section 1.5.2.

The commentary in the specification provides additional information about galloping. The commentary specifies that galloping produces the worst effects on nonsymmetrical cross sections when including the shape of the sign in the cross section. Four-chord COSS have a more symmetrical cross section than do two-chord COSS, when considering the sign in the cross section. For that reason, the commentary specifies that galloping can be ignored for four-chord COSS, which is why more state DOTs are opting for the four-chord COSS construction type over the two-chord design. Additionally, the four-chord COSS does not have the fatigue critical box-connection, instead using a collared plate connection.

1.5.2 – Fatigue:

Mechanical Behavior of Materials (Dowling 1999):

A structure's service life is a function of how adequately it can mitigate fatigue, where fatigue is the progressive deterioration of a material over time. Fatigue is caused by crack development at stress concentrations produced under cyclical loading. Cyclical stress range and the anticipated number of loading cycles are used in engineering designs of structures subjected to

repeated loading. Fabrication of metal connections involves welding together steel plates and drilling or punching holes for bolts. Both processes develop microscopic cracks in the connections. This is due to residual stresses caused by rapid heating and cooling, and material yielding exacerbating slip planes.

Fatigue cracks can develop in connections due to stress concentrations and the prevalence of connection features, such as welds or holes. Knowing the nominal cyclical stress and anticipated number of loading cycles, the fatigue life of a connection can be estimated. This is done using S-N (stress range-number of cycles) curves, which are based on categories of connections, by estimating the number of cycles until failure occurs under a certain stress range. Figure 1.5.2 shows AASHTO S-N curves for all detail categories (AASHTO 2015b). The fatigue performance of a connection is categorized as showing decreasing fatigue performance as reference lines move from A to E'. The horizontal lines represent a constant amplitude fatigue limit, such that a detail will not experience failure under that stress range.




Figure 1.5.2 – AASHTO S-N curves for all detail categories (AASHTO 2015b)

1.5.3 – Dynamic Properties:

Fundamentals of Structural Dynamics (Craig and Kurdila 2006):

Resonance is an important consideration in the design of structures with large spans and/or cantilevers, and is a phenomenon that occurs when the frequency of an oscillating load applied to a structure matches the structure's natural frequency. Even with seemingly insignificant loads, resonance can result in harmonic, large-amplitude motion with catastrophic consequences. A structure's natural frequency is a dynamic property derived from two characteristics: mass (m) and stiffness (k). Equation 1.5.3 defines a structure's natural frequency (f_n):

$$f_n = \frac{1}{2\pi} \sqrt{\frac{\text{stiffness}}{\text{mass}}} = \frac{1}{2\pi} \sqrt{\frac{k}{m}} \quad (1.5.3)$$

Damping (ζ) is not present in the relationship because damping reduces the amplitude of the response over time and does not affect natural frequency. Damping characterizes energy loss in a system, and cannot be derived from structural properties, unlike mass and stiffness. In most cases, a damping magnitude is assumed based on engineering judgment; otherwise, damping may be experimentally measured.

Most practical structures have multiple ways of deflecting due to varying directionally of loading. These structures are multiple-degree-of-freedom (MDOF) systems, meaning that they have more than one mode shape. A mode shape describes how a structure will deform under certain loading patterns, and each mode shape has an associated natural frequency. Mode shapes are activated under different loading conditions and result in different deflections and system behavior. Stiffness and mass are not isotropic; thus, the dynamic properties of a system change depending on the system's orientation. Structures with long spans and/or cantilevers have multiple ways of deflecting; thus, making them MDOF structures. Two-chord COSS are MDOF structures with two characteristic mode shapes defined in Section 2.2.

1.5.4 – Vortex Shedding:

Vortex shedding is an aeroelastic phenomena that can produce vibrations in structures to the point of extreme deflections and even failure. Vortex shedding occurs from the interaction of eddies and vortices that curl behind an object in a constant stream of fluid. The formation of eddies is caused by “a laminar boundary layer on the [edge of a surface that] often separates and forms a separated shear layer” (Yarusevych et al. 2009). This separation and creation of two different layers of flow are shown in Figure 1.5.4.1. and Figure 1.5.4.2.




Figure 1.5.4.1 – Flow layer development on an airfoil with a) separation and b) reattachment to the cross section (Yarusevych et al. 2009)




Figure 1.5.4.2 – Vortex shedding on a cylinder (Rice et al. 2008)

Figure 1.5.4.1 shows the effect of the air stream reattachment to the structure, which causes the curls in the wake of the shape in Figure 1.5.4.2. These curls represent shear, and if the developing shear begins to alternate symmetrically about a structure, movement will be induced (Holmes 2007). The eddies that form in the shear layer push on the edges of a structure incrementally, and if the oscillation of the eddy formation matches the structure's natural frequency, resonance can occur - especially in structures with long spans and cantilevers, such as cable-stayed bridges and sign structures. Infamously, the Tacoma Narrows Bridge collapsed in 1940 due to vortex shedding interacting with the long span of the bridge shown in Figure 1.5.4.3.




Figure 1.5.4.3 – Vortices interacting with the Tacoma Narrows Bridge cross section (Voss 2016)

Vortex shedding typically develops at constant wind speeds of 45 mph (20.1 m/s) or lower (AASHTO 2001) and vibrates a structure in a direction perpendicular to the flow. Vortex shedding typically affects shapes with large and smooth cross sections, such as large-diameter cylinders, but “can occur in other bluff bodies such as triangles, rectangles, or H and L shapes” (Kacin 2009). Monotube-style COSS and OSS have been especially susceptible to vortex shedding. Figure 1.5.4.4 and Figure 1.5.4.5 show the large deflections that can occur under vortex shedding, with the long, exposed cylindrical tube creating the conditions for this phenomenon.




Figure 1.5.4.4 - Monotube OSS experiencing vortex shedding (downward) (Mangat 2016)



Figure 1.5.4.5 - Monotube OSS experiencing vortex shedding (upward) (Mangat 2016)

AASHTO SLTS (AASHTO 2001) provides commentary describing when natural wind gusts can affect sign structures to the point of producing vortex shedding. If wind speeds are between 10 mph (4.47 m/s) and 45 mph (20.1 m/s) then vortex shedding has a higher probability of occurring (AASHTO 2001). Conditions tend to be too turbulent at wind speeds higher than 45 mph (20.1 m/s) to produce vortex shedding, and not significant enough to produce vortex shedding at wind speeds under 10 mph (4.47 m/s) (AASHTO 2001).

Although vortex shedding is not a common phenomenon, its effects can be catastrophic, so it is important to mitigate eddy interaction to combat this aeroelastic phenomena.

CHAPTER 2 – METHODS

This chapter describes the research methodology used in this investigation. Both analytical modeling techniques and experimental methods are detailed in this chapter.

2.1 Design Envelope and Model Selection

The Kansas Department of Transportation (KDOT) provided this project with construction specifications for two-chord COSS used in the KDOT highway inventory. The specifications include six “Dimension Design” groups, which define member sizes, dimensions, and spacing. A Dimension Design group is usually dependent on the size of the sign the two-chord COSS is supporting. Characteristics such as pole height, mast truss length, and sign size are site dependent, for which KDOT provided 110 examples of constructed COSS. From the specifications and constructed examples, three variable design characteristics were identified as shown in Figure 2.1.1: 1) sign size (x_1), 2) mast truss length (x_2), and 3) pole height (x_3). It is important to note that the sign’s aspect ratio (x_1/y_1) is generally dependent on the size of the sign. Large signs generally have lower aspect ratios where $x_1 \approx y_1$, while smaller signs generally have higher aspect ratios where $x_1 > y_1$.

The constructed examples display a wide range of variable design characteristics. Figure 2.1.3 shows a dimensional envelope derived from the 110 constructed examples provided by KDOT. Since the size of the sign usually determines the Dimension Design group for a given two-chord COSS, member section, dimensions, and spacing are all a function of the sign size. Because of this, changes in sign size are strongly correlated with structural mass and stiffness. The walkway has little effect on structural stiffness due to its connection to butterfly supports which are not critical to the structure.





Figure 2.1.1 – COSS variable design dimensions



Figure 2.1.2 – Constructed KDOT COSS



- Smallest Dimensions
- Largest Dimensions

Figure 2.1.3 – COSS dimensional envelope (based on 110 examples provided by KDOT)

Twenty-seven base models were created, to capture combinations of three sizes for the three variable design dimensions (sign size, x_1 & y_1 ; mast truss length, x_2 ; and pole height, x_3). The sizes chosen were intended to capture a range of small/short, medium, and large/long dimensions, based on the example set provided by KDOT. Medium values were chosen by calculating the rounded average of the constructed examples. Small (short) and large (long) values were chosen by the rounded-up standard deviation of the constructed examples in each direction. Table 2.1.1 shows the calculated values for each design parameter.

In addition to the twenty seven base models an additional five models representing extreme cases were added, which represented the smallest and largest bounds of the constructed examples

provided by KDOT (one of the constructed examples had both the shortest pole and shortest mast truss length which is why the addition is five and not six).

Because sign size is closely correlated with the dimensions of two-chord COSS, Table 2.1.2 outlines each of the member sections and number of butterfly supports based on sign size, while Table 2.1.3 outlines the member spacing as a function of sign size. This dimensional analysis yielded thirty-two sign structures that encompass the diverse dimensional parameters for KDOT two-chord COSS.

Table 2.1.1 – Design Parameter Values

| Characteristic | Small (Short) | Medium | Large (Long) |
|---|----------------------|-------------------|---------------------|
| | ft-in. (m) | ft-in. (m) | ft-in. (m) |
| Sign Length | 12'-0" (3.658) | 16'-0" (4.877) | 20'-0" (6.096) |
| Sign Height | 6'-0" (1.829) | 9'-0" (2.743) | 12'-0" (3.658) |
| Aspect Ratio, (x_1/y_1) | 2.0 | 1.8 | 1.7 |
| Mast Truss Length | 12'-0" (3.658) | 16'-0" (4.877) | 20'-0" (6.096) |
| Pole Height | 25'-0" (7.620) | 27'-0" (8.230) | 29'-0" (8.839) |

Table 2.1.2 – Member Sections Based on Sign Size

| Section | Small Sign | Medium Sign | Large Sign |
|----------------------------|-------------------|--------------------|-------------------|
| Chord | HSS8.625x0.5 | HSS10.75x0.307 | HSS12.75x0.375 |
| | (HSS21.91x1.27) | (HSS27.31x0.78) | (HSS32.39x0.95) |
| Web | HSS3x0.375 | HSS3x0.375 | HSS3x0.375 |
| | (HSS7.62x0.95) | (HSS7.62x0.95) | (HSS7.62x0.95) |
| Pole | HSS16x0.375 | HSS18x0.375 | HSS18x0.375 |
| | (HSS40.64x0.95) | (HSS45.72x0.95) | (HSS45.72x0.95) |
| Butterfly Supports* | Z4x8.2 | Z4x8.2 | Z4x8.2 |
| | (Z10.16x20.83) | (Z10.16x20.83) | (Z10.16x20.83) |

*Z-Shapes are similar to small wide flange beams, and not Z-Channels.

Table 2.1.3 – Member Spacing Based on Sign Size

| Section | Small Sign | Medium Sign | Large Sign |
|---|---------------|---------------|---------------|
| | ft-in. (m) | ft-in. (m) | ft-in. (m) |
| Vertical spacing between chords, A | 4'-0" (1.219) | 6'-0" (1.829) | 6'-0" (1.829) |
| Truss panel length, N | 7'-0" (2.134) | 7'-0" (2.134) | 7'-0" (2.134) |
| Spacing between butterfly supports, Z | 4'-6" (1.372) | 4'-4" (1.321) | 5'-8" (1.727) |
| No. of Butterfly Supports | 3 | 4 | 4 |

Model nomenclature represents the three variable design dimensions: x_1 & y_1 , x_2 , and x_3 .

The arrangement of the model nomenclature is shown below with x and y representing dimensions in feet:

$$Sx_1 \times y_1 - Lx_2 - Px_3$$

The first two values following S define the sign size, where x_1 defines the sign length, y_1 defines the sign height, and the “ \times ” separates the two dimensions. x_2 defines the mast truss length from the pole. Finally, x_3 defines the pole height. Figure 2.1.1 displays where the dimensions correspond on a two-chord COSS.

2.2 Characteristic Mode Shapes

Two-chord COSS have two characteristic modes. These modes are characterized by different deflections and are activated under different loading scenarios. The two modes are dramatically different and produce peak stresses in different locations in COSS members and connections. These critical loads come from wind, which is random in nature and can cause harmonic responses under certain aeroelastic phenomena.

The first characteristic mode has a torsional mode shape and is produced at the lowest natural frequency of all two-chord COSS systems. In this torsional mode, the sign and mast truss rotate about the fixed pole. This mode is activated by natural wind gusts, and can cause large, out-

of-plane stress concentrations in the connection between the pole and mast arms. Figure 2.2.1 and Figure 2.2.2 display the torsional mode shape.




Figure 2.2.1 – Torsional mode shape (3D perspective view)




Figure 2.2.2 – Torsional mode shape (top-down view)




Figure 2.2.3 – Chopping mode shape (3D perspective view)




Figure 2.2.4 – Chopping mode shape (front-on view)

The second characteristic mode has a distinct “chopping” mode shape and occurs at the second lowest natural frequency of all two-chord COSS systems. In the chopping mode, the sign and mast truss displace vertically in-plane with the pole. This mode is activated by truck-induced wind gusts and global and local vortex shedding. Global vortex shedding can occur in the wake of

the sign, while local vortex shedding can occur in the wake of both chords. The chopping mode can produce large, in-plane stress concentrations in the connection between the pole and mast arms. Figure 2.2.3 and Figure 2.2.4 display the chopping mode shape.

Both of these characteristic modes are investigated as removal of the walkway results in a significant mass loss on the end of the cantilever. The end of a cantilever is the most influential part when investigating the effect mass has on a systems response frequency. The removal of the walkway has little effect on the stiffness of the system, since it is not directly connected to any critical members.

2.3 Finite Element Modeling – Fundamental Frequencies

The commercially-available finite element software package, Abaqus/CAE 2016 (DSS 2014) was used to create 3D, linear-elastic, finite element models of the thirty-two COSS described in Section 2.1.

2.3.1 – Part and Assembly Creation and Meshing:

Five parts were created for each COSS model. The butterfly supports, mast truss, and pole were modeled using wire elements with sections defined from the construction specifications provided by KDOT. The mast truss, which includes the two tube chords and pipe diagonals, was created as one part, as opposed to separate parts and brought into the assembly for later connectivity. The sign was modeled with infinitely stiff, 3D shell elements with a thickness of 1/16” (0.159 cm). In practice, large, overhead signs are created with aluminum channels where the flanges are bolted together to achieve the desired height and thus are quite rigid. In addition, the signs are laterally supported along the bottom chord, which provides additional stiffness. The

walkway was also modeled with infinitely stiff, 3D shell elements, here with a thickness of 1 1/2” (3.81 cm). The sign and walkway were modeled as having infinite stiffness to help mediate local vibrations contributing to global response frequencies. To consider the validity of these simplifications, the dynamic properties of the COSS were also computed using the specified material stiffness, and the global dynamic properties were negligibly affected as compared to the models with infinite stiffness parameters defined for the sign and walkway. All five parts were initialized into the assembly and placed according to the specifications.

After the parts were created and sections and orientations were assigned, the parts were assigned a mesh. Meshing is generally not critical for frequency steps and should be assigned based on the complexity of a member (DSS 2015). Linear-beam meshing techniques were applied to the butterfly supports, mast truss, and pole due to the parts being wire elements. Quad-dominated meshing techniques were applied to the sign and walkway. The typical mesh density used for each part (nodes are highlighted) is shown in Figure 2.3.1. All five parts’ mesh were sized controlled, and Table 2.3.1.1 outlines the seed size of each part.

Table 2.3.1.1 – Part Meshing Seed Size

| Part | Seed Size |
|--------------------------|------------------|
| | in. (cm) |
| Sign | 10.0 (25.4) |
| Butterfly Support | 4.00 (10.2) |
| Mast Truss | 4.00 (10.2) |
| Pole | 12.0 (30.5) |
| Walkway | 10.0 (25.4) |




Figure 2.3.1 – Typical mesh used for each part in the COSS dynamic models: a) sign, b) walkway, c) butterfly support, d) pole, and e) mast truss

2.3.2 – Material Definition:

Two materials were used for the modeling of the COSS in accordance with the construction specifications. The pole, mast truss, butterfly supports, and walkway were modeled with nominal linear-elastic properties for steel, while the sign was modeled with nominal linear-elastic properties for aluminum. Table 2.3.2.1 outlines the materials and their pertinent properties (ASTM A709/A709M-18 2018) (ASM International 1990). It is important to note that the construction

specifications allow for either a steel or aluminum walkway, but steel was chosen due to its higher density, resulting in a greater effect on the reduction of mass when removed.

Table 2.3.2.1 – Dynamic Modeling Material Properties

| Material | Description | ρ | E | ν |
|----------|-------------|---|-------------|-------|
| | | lb/ft ³ (kg/m ³) | ksi (GPa) | - |
| Steel | A709 Gr. 36 | 490.0 (7849) | 29000 (200) | 0.29 |
| Aluminum | 6061-T6 | 168.5 (2699) | 10150 (70) | 0.33 |

2.3.3 – Connections and Boundary Conditions:

All connections between parts were modeled using tied constraints, which is reasonable referencing the construction specifications. Below is a list of all the connections and how they were modeled:

- 1) Connections between pipe diagonals and tube chords (mast truss) – wire part tied constraint – the end nodes in the pipe webs were connected to corresponding nodes in the tube chords to create a single, rigid part.
- 2) Connections between the walkway and butterfly supports – surface to node region tied constraint – the wire elements in the butterfly supports’ horizontal members contacting the walkway were master node regions, and the bottom of the walkway was taken to be the slave surface.
- 3) Connections between the sign and the butterfly supports – surface to node region tied constraint – the wire elements in the butterfly supports’ vertical members contacting the sign were made master node regions, and the surface facing the butterfly supports was the slave surface.

- 4) Connections between the butterfly supports and mast truss – node region to node region tied constraint – the wire elements in the chords of the mast truss contacting the butterfly supports were assigned as master node regions, and the wire elements in the butterfly supports' vertical members contacting with the chords of the mast truss were slave node regions.
- 5) Connections between the mast truss and pole – node region to node region tied constraint – the wire elements in the pole contacting the chords of the mast truss were master node regions, and the two end nodes in the mast truss contacting the pole were slave node regions.

The base of the pole was modeled as a fully-fixed support.

2.3.4 – Step Creation:

Natural frequencies were computed using a frequency step with computations performed using linear perturbation. After the natural frequencies were computed, the walkway was removed from the assembly along with Constraint 1 from Section 2.3.3 and the model execution was repeated. Therefore, natural frequencies were determined for each model geometry twice – once with the walkway in place, and once with the walkway removed. The mass percentage of the walkway when compared to the whole system was recorded as well.

2.4 Loading Methodology

To analyze how the walkway attachment affects the aerodynamic shape of the sign, a two-step approach was taken, utilizing computational fluid dynamics models and dynamic structural models. The computational fluid dynamics models were created to determine the forces acting on

the sign under different wind velocities, and to examine interactions between the sign (with and without the walkway) and wind. This done by modeling the influential part of the sign structure as a void space in a fluid domain. However, it is extremely difficult to also capture structural interactions within a computational fluid dynamics model. Therefore, dynamic structural models were also utilized to examine structural responses (such as in plane vibrations and associated stresses stimulated by aeroelastic phenomena) of the overall COSS under time history loadings extracted from the computational fluid dynamics models. Therefore, the first step was to create computational fluid dynamics (CFD) models of the COSS and extract member forces induced by wind across a time history. The second step was to apply those extracted forces from the CFD models and apply them as time-dependent loads within the dynamic structural models. Figure 2.4.1 outlines the methodology framework.




Figure 2.4.1 – Methodology framework

This process can be described as quasi-fluid-structure-interaction, since the whole sign structure was not modeled in the fluid domain in the CFD analysis. Figure 2.4.2 highlights the influential surfaces investigated between the two models. Detailed descriptions of the modeling techniques are described in the subsequent section.




Figure 2.4.2 – Investigated surfaces between the dynamic loading model (left) and the CFD model (right)

2.4.1 – Design Loads and Wind Speed Selection:

AASHTO LRFD Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2015 First Edition (AASHTO 2015a) in conjunction with American Society of Civil Engineers (ASCE) 7-10: Minimum Design Loads for Buildings and other Structures (ASCE 2010) define the wind loads that COSS must be designed to resist.

Equation 2.4.1.1 defines the design wind pressure and is derived using standard air (defined in Section 2.5.1) and the theoretical pressure equation for a fluid contacting a surface shown in Equation 2.5.4.1. The resulting Pressure (P) is a function of the fluid's density (ρ) and the speed at which the fluid is moving (V).

$$P = \frac{1}{2}\rho V^2 \quad (2.4.1.1)$$

Equation 2.4.1.2 is defined in ASCE 7-10 and calculates the design wind pressure for a structure. This equation takes into effect the structure's location, height, surrounding features, and dynamic response, giving it more factors than the previous equation. The first factor in Equation 2.4.1.2 (0.00256) equals half of the density of air multiplied by the squared conversion of mph to ft/s (this factor changes to 0.613 for SI units). The design wind pressure (P_z) is calculated in psf using the basic wind speed (V) in mph. K_z , K_d , G , and C_d are all unitless factors and coefficients and are defined in Table 2.4.1.

$$P_z = 0.00256K_zK_dGV^2C_d \quad (2.4.1.2)$$

Table 2.4.1 – Wind Pressure Equation Calculated Factors and Coefficients

| Factor/Coefficient | Variable | Value |
|----------------------------|----------|-------|
| Height and Exposure Factor | K_z | 0.94 |
| Directionality Factor | K_d | 0.85 |
| Gust Effect Factor | G | 1.14 |
| Drag Coefficient | C_d | 1.18 |

Kansas DOT's COSS are designed to resist a 105 mph (46.9 m/s) wind speed for natural wind loading, which corresponds to a wind load of 30.4 psf (1460 Pa). Changing the wind speed in Equation 2.5.4.2 results in a second order change in the design wind pressure.

The Gust Effect Factor which combines the dynamics of a structure with its design wind load (more rigid structures have lower Gust Effect Factors), was calculated using Section 26.9 in ASCE 7-10. It is typically used if a structure has a natural frequency lower than 1 Hz, which is characteristic for some two-chord COSS. The Gust Effect Factor is a function of the natural frequency of a structure and the height of the influential area. The Gust Effect Factor was

calculated to be less than the minimum of 1.14, so 1.14 was used. The mean hourly wind speed (\bar{V}_z) was calculated in the process and was determined to be 61.2 mph (27.4 m/s). The mean hourly wind speed is an important value because it defines the average wind speed a structure is likely to see at the structure's height during severe weather events. The average sign height defined in Section 2.1 was used to compute the mean hourly wind speed.

Three wind speeds were ultimately chosen for investigation: 1) 105 mph (46.9 m/s), 2) 61.2 mph (27.4 m/s), and 3) 30 mph (13.4 m/s) representing: 1) the basic design wind speed, 2) the mean hourly wind speed, and 3) a relatively equidistant lower wind speed, respectively.

2.5 Computational Fluid Dynamics (CFD) Modeling

The commercially-available Abaqus/CFD 2016 finite element analysis software (DSS 2014) was used to create computational fluid dynamics models to quantify the forces that developed in the COSS from natural wind gusts. The CFD Models were also used to examine changes in the aerodynamic behavior of the sign structures with removal of the walkway. It is important to note that the CFD models are time dependent, allowing aeroelastic phenomena, such as vortex shedding, to be observed.

The CFD models included the sign, chords directly behind the sign, butterfly supports, and walkway attachment, which together are referred to as the “Shape” herein. The pole, webbing in the mast truss, and chords connecting the sign and pole were excluded from the CFD model for simplicity and convergence. This portion of the COSS is at the end of the cantilever and experiences the most significant loading when compared to the rest of the structure, making it the most influential part for stress development in the connections. Additionally, the walkway only

spans in the Shape's domain, and has no effect on the aerodynamic behavior of the pole or mast truss connecting the sign and the pole.

Since the mast truss and pole were omitted from the CFD models, the sign size and presence of a walkway attachment were the influential design characteristics captured in the fluid domain. The three sign sizes from the construction specifications, two attachment conditions, and three wind speeds defined in Section 2.4.1 accounted for the 18 CFD models that were constructed. The model creation process was similar across the different sign sizes and attachment conditions. The fluid domains were the same for each wind speed. Different wind speeds only changed the velocity and the time period.

2.5.1 – Defining CFD Interaction Surfaces and Material Definition:

Important characteristics of the CFD models were defined before modeling commenced. Air is a compressible fluid, and its material properties change with atmospheric temperature and pressure. Atmospheric pressure and temperature can vary dramatically throughout the year, resulting in a change of density of $\pm 10\%$. (Hall 2015). Because of this, standard air was modeled. Standard air has a pressure of 14.7 psi (1 atm) and a temperature of 59° F (15° C). The properties used for air in the CFD are detailed in Table 2.5.2.1 (Hall 2015) (Kadoya et al. 1985).

Table 2.5.2.1 – CFD Material Properties

| Material | Description | ρ | μ |
|----------|--------------|---|---|
| | | lb/ft ³ (kg/m ³) | lb·s/ft ² (Pa·s) |
| Air | Standard Air | $2.37 \cdot 10^{-3}$ ($3.80 \cdot 10^{-2}$) | $3.785 \cdot 10^{-7}$ ($1.789 \cdot 10^{-5}$) |

The various surfaces in the CFD model were examined to determine how forces changed on the sign over time. These surfaces were: a) sign face, b) back of sign, c) top of sign, d) bottom of sign, e) top chord, f) bottom chord, g) top of grate, and h) bottom of grate, and are shown in Figure 2.5.1.1. Surfaces g) and h) did not exist in the CFD models without the walkway attachment. The vertical sides on the sign, walkway attachment, and chords were ignored for data extraction due to the symmetry of the fluid domain, and pressure applied to the vertical edges of the dynamic loading models would have a negligible effect on the torsional and chopping modes. The butterfly supports were ignored for data extraction, since the sections are very small resulting in negligible forces.




Figure 2.5.1.1 – Influential surface locations used for force extraction from the CFD models: a) sign face, b) back of sign, c) top of sign, d) bottom of sign, e) top chord, f) bottom chord, g) top of grate, and h) bottom of grate

2.5.2 – Part and Assembly Creation, and Boundary Condition Selection:

The fluid domain for a CFD model can be very sophisticated, especially if the domain is fluid moving around an object and not fluid moving through a space. Research performed by Chao et al. (2016) aimed to accurately describe the force applied by wind loading on large signs. They achieved this by creating a CFD model of a very simple sign shape. The CFD modeling was done using CFX by Ansys and the fluid domain is shown in Figure 2.5.2.1. Chao et al. (2016) described the steps to produce a typical fluid domain around a large sign shape. There are two important steps for correct fluid domain creation: 1) void space modeling and 2) boundary condition selection. In particular:

- 1) The Shape to be investigated should be modeled and cut from a larger domain, leaving behind walls or void spaces that match the original Shape.
- 2) Boundary conditions are the exterior faces of the larger domain. The faces should be far enough away so that turbulence does not experience boundary effects.




Figure 2.5.2.1 – CTX fluid domain (Chao et al. 2016)

If a modeled Shape is too near a boundary condition, wakes and eddies will contact the boundary faces and produce boundary effects. The effects will likely result in model divergence as the low pressure turbulence contacting an inlet/outlet condition will cause cavitations. Model

divergence results in invalid data or model instability. This is most important for the fluid outlet boundary condition due to the significant turbulence in the wake of a flat plate. The outlet boundary condition should be placed approximately eight times further away from the Shape than the fluid inlet.

The type of boundary condition is important, as well. If surrounding boundary conditions (other than the inlet and outlet) are modeled as no-slip walls, turbulence from the walls will act in conjunction with turbulence from the Shape, creating a faux-bottleneck condition which increases the fluid's speed around the Shape. Therefore, boundary conditions other than the inlet and outlet should be modeled as slip walls, or as having pressurized inlet/outlet conditions.

A study performed by Gemba (2007) described the boundary layer created by flow over a flat plate, and investigating functions to describe its shape in both laminar and turbulent flow. A boundary layer inherently grows as it moves past its influential shape. It shifts from laminar to turbulent flow, as shown in Figure 2.5.2.2. The boundary layer thickness is important to estimate to mitigate boundary effects for both CFD modeling and wind tunnel testing.




Figure 2.5.2.2 – Profile of flow over a flat plate (Gemba 2007)

Equation 2.5.2.1 and Equation 2.5.2.2 can be used to estimate the boundary layer thickness (δ) as a function of distance away (L) from the influential area for laminar and turbulent flow, respectively.

$$\delta_L = 5L / \sqrt{Re} \quad (2.5.2.1)$$

$$\delta_T = 0.382L / \sqrt[5]{Re} \quad (2.5.2.2)$$

The Reynolds number (Re) is an important constant in these equations as it characterizes the flow as laminar or turbulent. The Reynolds number of a fluid is defined by equation 2.5.2.3, and its variables are defined in Table 2.5.2.1 for standard air.

$$Re = \frac{\rho VL}{\mu} \quad (2.5.2.3)$$

Table 2.5.2.1 – Reynolds Number for Standard Air (CFD Modeling)

| Variable | Notation | Value | Units (S.I.) |
|--------------------------------|----------|---|---|
| Density | ρ | $2.37 \cdot 10^{-3}$ ($3.79 \cdot 10^{-2}$) | lb/ft ³ (kg/m ³) |
| Velocity* | V | 44 (13.4) | ft/s (m/s) |
| Characteristic Length** | L | 0.125 ($3.81 \cdot 10^{-2}$) | ft (m) |
| Dynamic Viscosity | μ | $3.785 \cdot 10^{-7}$ ($1.789 \cdot 10^{-5}$) | lb·s/ft ² (Pa·s) |
| Reynolds Number | Re | 34400 | - |

*30 mph = 44 ft/s (13.4 m/s)

**1.5 in. = 0.125 ft (3.81 cm)

The lower the fluid's velocity, the larger the boundary layer thickness, and because of this the lowest wind speed was chosen for this calculation. In this application, the characteristic length is the thickness of the sign. Using the Reynolds number for a wind speed of 30 mph (13.4 m/s) and a characteristic length of 1.5 in. (38.1 mm), a turbulent boundary layer thickness (δ_T) was computed as a function of distance away from the Shape (L). This is shown in Equation 2.5.2.4:

$$\delta_T = 0.0473L \quad (2.5.2.4)$$

The turbulent boundary layer is critical for CFD modeling because turbulence can cause cavitation conditions which results in model instability (Chao et al. 2016). Although this expression estimates the size of the turbulent boundary layer, it is suggested that a larger distance be used.

One part was created which was used as the fluid domain for the assembly, the process for which is shown in Figure 2.5.2.3. The domain was created by modeling a large, rectangular fluid domain (a) and cutting out the filled Shape (b); thus, resulting a fluid domain around the Shape (c). The fluid domain was modeled as a solid object encompassing the air around the Shape.




Figure 2.5.2.3 – Fluid domain creation: a) full fluid domain, b) filled shape, and c) resulting fluid domain

Below is a list of the boundary conditions that were assigned to the resulting fluid domain, and their distance to the Shape denoted by δ_n :

- 1) Walls and ceiling – fluid inlet/outlet condition – specified pressure of 14.7 psi (1 atm),
 $\delta_{\text{walls}} = 0.6 \cdot (\text{Sign Length})$, $\delta_{\text{ceiling}} = 1.5 \cdot (\text{Sign Height})$.
- 2) Ground – no slip fluid wall condition – $\delta_{\text{ground}} = 17' - 4''$ (5.28 m). δ_{ground} is defined in the construction specifications.
- 3) Inlet – fluid inlet/outlet condition – specified velocity (see Section 2.4.1), $\delta_{\text{inlet}} = \text{Sign Height}$.

- 4) Outlet – fluid inlet/outlet condition – specified pressure of 14.7 psi (1 atm), $\delta_{\text{outlet}} = 8 \cdot \delta_{\text{inlet}}$ (DSS 2015).
- 5) Sign Interface – no slip fluid wall condition – these boundaries are walls in the fluid domain.

Dimensions of the boundary conditions were initially selected using Equation 2.5.2.4 with an additional 2 ft (0.61 m) added to the calculation. Even with the extra distance, some models still experienced boundary interactions at 30 mph (13.4 m/s). To resolve this, additional space was formulated to create the rules defined in boundary condition distances (1) and (3).

2.5.3 – Fluid Domain Meshing:

All of the CFD models utilized large, sophisticated domains, which required careful meshing techniques. In Abaqus/CFD 2016, data can only be extracted at nodes (not elements), so faces cannot be defined for data extraction. To determine the forces resulting on the Shape from natural wind gusts in the CFD simulations, nodes were carefully spaced such that forces at nodes could be easily multiplied by the element's area to obtain pressures. Additionally, Abaqus/CFD 2016 produced the best results with a hex-mesh. (DSS 2015) Because of this, a hex-mesh technique was assigned. This could only be done after systematic partitioning of the fluid domain. Every face created by the cut-out region of the Shape in the fluid domain was extended to create a partition in the fluid domain. A typical, final extension-partitioned fluid domain is shown in Figure 2.5.3.1. This step creates geometrically sound baselines for seed propagation, and is the only way a hex-meshing technique was able to be applied to this type of domain. The mesh size was size controlled using 3" (7.62 cm) seed size. Nodes on the Shapes' surfaces were grouped by elemental area before the model was executed.




Figure 2.5.3.1 – Typical partitioned fluid domain

Regions directly surrounding the Shape were the most important to monitor. Regions nearer to the boundaries were of less interest, other than checking for convergence and mitigating boundary interactions. Because of this, the mesh was assigned an increased size around the perimeter of the fluid domain to improve efficiency of the model executions. The mesh size was increased to a 9 in. (23 cm) seed size in these areas. Figure 2.5.3.2 shows the mesh for a typical CFD model with a walkway attachment, and Figure 2.5.3.3 shows the mesh for a typical CFD model without an attachment. Note, both figures are zoomed in, and do not show the full domain for the sake of clarity.




Figure 2.5.3.2 – Typical fluid domain mesh with walkway attachment




Figure 2.5.3.3 – Typical fluid domain mesh without walkway attachment

2.5.4 – Step Creation and Turbulence Modeling Parameters:

Each CFD model underwent a time history flow step with a fixed time increment size of 0.01 seconds. The models' time period was selected based on how long it took the model to produce a constant laminar flow in the wake of the sign, rounded up to the nearest half second. Table 2.5.4.1 presents the time period modeled at the desired wind speeds in the CFD analysis.

Table 2.5.4.1 – CFD Model Time Period Definition

| Wind Speed | CFD Time Period |
|--------------------|------------------------|
| mph (m/s) | s |
| 105 (46.9) | 2.5 |
| 61.2 (27.4) | 3 |
| 30 (13.4) | 5 |

Turbulence modeling is an important and complex feature of CFD programs and is a function of the fluid being modeling, the fluid speed, the fluid domain, and expected turbulence. Most turbulence modeling modules in CFD programs require constants to be defined before the model is processed. These constants stem from fluid properties to eddy propagation. Generally, the more complex a model, the more calibration is required for valid results. For example, modeling a hot

tub would require intensive investigation and iteration of turbulence modeling due to complex interactions such as heat transfer, dual-material interaction, prevalence of air in the fluid, and tri-axial inlets.

Although the CFD models being created in this research project are unusual in nature, the Shapes in the domain are simple and large, which produce simple vortices in the wake of the Shape. Additionally, the fluid was modeled as a homogenous material, wind speeds were kept constant, and boundary effects were mitigated. Ultimately, the turbulence was experienced to be simple. For this reason, default turbulence modeling parameters were selected. The default is Spalart-Allmaras turbulence modeling, and the constants prescribed with this technique have been defined in Table 2.5.4.2.

Table 2.5.4.2 – Spalart-Allmaras Turbulence Modeling Constants (DSS 2015)

| Constants | Value |
|-----------------------|--------------|
| C_{b1} | 0.1355 |
| C_{b2} | 0.622 |
| C_{v1} | 7.1 |
| C_{v2} | 5 |
| C_{w1} | 3.2391 |
| C_{w2} | 0.3 |
| C_{w3} | 2 |
| σ | 0.6667 |
| K | 0.41 |

Because turbulence was being modeled, all inlet/outlet boundary conditions needed to be defined with kinematic eddy viscosities. This defines how turbulent the flow is as it enters the domain. The CFD models in this research utilized constant, laminar wind speeds; therefore, all kinematic eddy viscosities needed to be a small, non-zero value; 0.01 in.²/s ($6.45 \cdot 10^{-6}$ m²/s) was selected.

Three variables were defined in the field output request: pressure, velocity, and vorticity. Variables for the solver equations for the field output request were defined through an iterative process that produced model convergence. Table 2.5.4.2 defines these variables for the time history flow step. These variables were maintained the same for each CFD model and for each wind speed.

Table 2.5.4.2 – CFD Model Solvers’ Variables Definition

| Solver | Momentum Equation | Pressure Equation | Transport Equation |
|---------------------------------------|--------------------------|--------------------------|---------------------------|
| Iteration Limit | 600 | 1200 | 600 |
| Convergence Checking Frequency | 1 | 10 | 1 |
| Linear Convergence Limit | $1 \cdot 10^{-12}$ | $1 \cdot 10^{-14}$ | $1 \cdot 10^{-12}$ |

With converged output files from the CFD models, time history forces were extracted from the influential surfaces defined in Section 2.5.1. Additional data, both qualitative and quantitative, could also be extracted and observed anywhere in the fluid domain across the time history. This includes (but is not limited to) pressure heat-maps of the influential surfaces, velocity profiles around the sign, velocity vector outputs, eddy location and propagation, critical eddy interaction, porosity of the grate, and vorticity. See Appendix A1 and A2 for eddy interaction and velocity profile data.

2.6 Finite Element Modeling – Dynamic Loading

Using the same Abaqus/CAE 2016 models used to determine the fundamental frequencies (described in Section 2.3), in conjunction with the time-dependent forces extracted from the Abaqus/CFD 2016 models described Section 2.5, dynamically-loaded models were constructed.

Only the 27 base models described in Section 2.1 were modeled dynamically, and not the five extreme case models. This is because the CFD models only captured the small, medium, and large sign sizes, and not the additional five unique sizes considered in the extreme case models. The 27 base models, two grate conditions (with grate vs. without grate), and loading at the three specified wind speeds accounted for 162 dynamically-loaded structural models. The only changes to the Abaqus/CAE 2016 models from Section 2.3 and the dynamic loading models in this section were the step creation and time-dependent load application.

2.6.1 – Step Creation and Load Application:

The step was changed from the frequency step used in prior models to a dynamic, implicit loading step. The time period used for the dynamic loading step matched the output from the CFD models for the respective wind speed outlined in Table 2.5.4.1, as well as the fixed time increment size of 0.01 seconds. Stresses, strains, displacements, forces, and reactions were the variables defined in the field output request.

Loads were modeled as a uniform unit load (with a value of 1) on the respective part in the structural model. The unit loads would be later multiplied by the imported amplitudes from the CFD data. The top and bottom chord loads were modeled as being loaded by uniform line loads. The sign face, back of sign, top of grate, and bottom grate loads were loaded with uniform pressures. The top of sign and bottom of sign loads were modeled as uniform shell edge loads. The

loads from the CFD data were imported as smooth step amplitudes. The amplitudes were then multiplied to each unit load from the influential surface for the given wind speed on the respective part.

Displacements in the Y and Z direction at the top chord in the mast truss at the end of the cantilever were extracted. Stresses in both box-connections and at the base of the pole were also extracted. After the results were computed for the COSS with the walkway, the walkway was removed from the assembly along with Constraint 1 from Section 2.3.3, and the model was executed in the new geometric configuration. The updated displacements and stresses were recorded, producing two data sets for every sign geometry considered.

2.7 Experimental Methods

Experimental testing was conducted to validate and contextualize the CFD modeling results. The experimental testing consisted of wind tunnel tests with the goal of determining forces acting on the sign at various wind speeds. A scale model sign Shape was constructed, supported in a wind tunnel, and subjected to multiple wind speeds. Both qualitative and quantitative data were collected from the wind tunnel testing, but due to physical limitations, some of the data observed in the CFD modeling was unable to be observed in the experimental testing (such as pressure heat-maps or velocity profiles). The quantitative data collected from wind tunnel testing consisted of force data collected at different wind speeds. The qualitative data consisted of turbulence prevalence, which revealed eddies and vortices.

2.7.1 – Scale Model Construction:

Similar to the Shape modeled in the CFD analyses, the scaled physical model did not include the pole, webbing in the mast truss, or chords connecting the sign to the pole. The scaled model included the sign, three butterfly supports, and walkway attachment (grate). The chords were excluded to simplify the contact connection from the scaled model to the load cells. (It is important to note that the chords were found to not have experienced significant forces in the CFD analysis.)

The wind tunnel used for the experimental testing had a closed, 4 ft. (1.22 m) x 3 ft. (0.91 m) cross sectional testing area. Although the scaled model was significantly smaller than its constructed counterpart, significant forces can still develop, especially at higher speeds (Barlow 1999). For this reason, similar materials from the construction specifications were selected for the scaled model, and for the sake of structural integrity. The sign was made out of aluminum, and the butterfly supports and walkway components were steel.

The large sign size was selected (from Section 2.1) to be investigated in the wind tunnel testing. This was partially to accommodate potential future testing of smaller sign sizes, which could be accommodated in the wind tunnel at the same scale of the large sign size. Using the same process in Section 2.5.2, the boundary layer thickness for wind tunnel testing was estimated. Unlike the CFD modeling, the laminar boundary layer was critical due to its stronger boundary interaction. Boundary interactions from turbulent boundary layers are relatively small, and do not affect experimental models (Barlow 1999).

Table 2.7.1 – Reynolds Number for Standard Air (Wind Tunnel Testing)

| Variable | Notation | Value | Units (S.I.) |
|--------------------------------|----------|---|---|
| Density | ρ | $2.37 \cdot 10^{-3}$ ($3.79 \cdot 10^{-2}$) | lb/ft ³ (kg/m ³) |
| Velocity* | V | 7.333 (2.235) | ft/s (m/s) |
| Characteristic Length** | L | 0.0417 (0.0127) | ft (m) |
| Dynamic Viscosity | μ | $3.785 \cdot 10^{-7}$ ($1.789 \cdot 10^{-5}$) | lb·s/ft ² (Pa·s) |
| Reynolds Number | Re | 1910 | - |

*5 mph = 7.333 ft/s (2.24 m/s)

**0.5 in. = 0.0416 ft (12.7 mm)

Using the Reynolds number for a wind speed of 5 mph (2.24 m/s) (5 mph was the lowest wind speed for wind tunnel testing) and a characteristic length of 0.5 in. (12.7 mm) (0.5 in. was the thickness of the scale model sign), a laminar boundary layer thickness (δ_L) was derived as a function of distance away from the model sign (L). This is shown in Equation 2.7.1:

$$\delta_L = 0.114L \quad (2.7.1)$$

The laminar boundary layer thickness was calculated to be 4.3 in. on each side of the sign to mitigate boundary effects up to 3 ft (0.91 m) downwind of the test set up. The thickness was rounded up to 6 in. The sign's length controlled the scale, which was selected at a 20:3 size reduction. See Appendix B for the construction drawings of the scaled sign.

The scaled model aluminum sign imitated the shape of the construction specifications, and not the CFD model. The aluminum sign piece, even at a 20:3 scale, would be too heavy to hang if it was a solid piece. The construction specifications called for extruded aluminum channels to compose the sign. The channels are connected to each other with bolts through their flanges, as shown in Figure 2.7.1.1. The aluminum sign piece imitated this by attaching aluminum bars to the back of the aluminum sheet shown in Figure 2.7.1.2. The ribbing was attached to the aluminum sheet using a two-part adhesive epoxy. The scaled aluminum sign piece was bolted to the butterfly

supports with angled wooden blocks between the two pieces. The wooden blocks gave the sign its necessary 4% tilt.




Figure 2.7.1.1 – Constructed extruded aluminum sign (LA DOT)



Figure 2.7.1.2 – Physical scaled sign model

Although the construction specifications call for Z-Shapes (similar to small wide flange beams, and not Z-channels) for the butterfly supports, it is commonplace to use similarly-sized square HSS in the field. The scale model used scaled square HSS sections for the butterfly supports. The connection between the vertical and horizontal square HSS were welded together. Only three butterfly supports were constructed instead of four to allow for easier walkway attachment connectivity.

The scaled model walkway was constructed to have a similar porosity as walkways used in the field. The walkway was constructed out of small steel bars. The bars were notched and then welded together at each intersection. The walkway was attached to the butterfly supports with zip ties for easy removal and reattachment. The heads of the zip ties were tucked into the voids of the scaled walkway.




Figure 2.7.1.3 – Scaled model used for experimental testing in the wind tunnel

2.7.2 – *Experimental Setup:*

Two series of experimental tests were conducted in the wind tunnel. The first series of tests was aimed at collecting forces acting on the sign, produced by different wind speeds. These forces were measured through use of load cells. Forces were recorded at wind speed increments of 5 mph (2.24 m/s), starting at 10 mph (4.47 m/s) and capping at 40 mph (17.88 m/s). Each wind speed increment was repeated three times. The test series was limited to a maximum wind velocity of 40 mph due to the turbulence caused by the large shape in the wind tunnel. The second series of tests involved observing this turbulence through use of fog and lasers. Videos were recorded during this test, and qualitative data was collected. Due to sensitive instrumentation in the wind tunnel, this test was only conducted at a wind speed of 5 mph (2.24 m/s). Both test series were conducted both with and without the walkway attachment to observe its influence on the results.

The scaled model was hung in the wind tunnel using a system of rollers. Figure 2.7.2.1 shows a schematic of the restraints used in the wind tunnel, and Figure 2.7.2.3 shows the actual test setup. The rollers only supported the sign in the y-direction and were greased to mitigate friction forces in the x-direction. Three load cells were placed behind the scaled model facing the

x-direction, their contact locations shown in Figure 2.7.2.2. The three load cells behind the sign captured the forces that developed under the action of the experimental wind gusts. A fourth load cell was placed underneath the sign in the y-direction. This load cell never came into contact with the sign assembly during the tests and served as a vestigial instrument to record data if the scale model dislodged from the test set-up.




Figure 2.7.2.1 – Wind tunnel test setup connectivity




Figure 2.7.2.2 – Load cell locations, behind the sign face



Figure 2.7.2.3 – Experimental test setup

A fog machine was placed upstream of the scale model in the wind tunnel. The wind tunnel used recycles the circulating air, yielding a uniformly translucent gas. A laser was placed outside of the wind tunnel pointing into the testing area. The laser illuminated a plane where incongruities

in the fog could be easily seen. The incongruities in the fog displayed eddies and vortices created by the presence of the scaled model. The laser plane was placed in front of the model, at the sign face, and behind the model. Figure 2.7.3 displays the laser plane used in this portion of the experimental testing.




Figure 2.7.2.2 – Typical laser plane (placed at the model sign face)

CHAPTER 3 – RESULTS

In this chapter, the data produced from the finite element models and the experimental wind tunnel testing is summarized. In each section, trends are identified in the data. Due to the number of models produced from the dimensional analysis, most of the comparison data is graphed with respect to the walkway attachment's mass in terms of a percentage of the system mass. Trends are better observable with this variable chosen as the control.

3.1 Finite Element Modeling – Fundamental Frequencies of the COSS

All 32 models' modal response frequencies were computed, both with and without a walkway, as shown in Table 3.1.1. Changes in mass resulted in changes in the modal frequency, as defined in Equation 1.5.3. Mass and stiffness changed with each model, but only the mass significantly changed upon removal of the walkway.

Table 3.1.1 – COSS Modeled Natural Frequencies

| Model | walkway mass % | with walkway | without walkway | Δ | with walkway | without walkway | Δ |
|-----------------------|-------------------|-----------------|--------------------|----------|-----------------|--------------------|----------|
| | % | Hz. | Hz. | % | Hz. | Hz. | % |
| S20x12-L20-P25 | 4.63% | 0.87 | 0.91 | 4.31% | 1.25 | 1.30 | 4.35% |
| S20x12-L20-P27 | 4.52% | 0.84 | 0.88 | 4.26% | 1.17 | 1.21 | 3.79% |
| S20x12-L20-P29 | 4.45% | 0.81 | 0.85 | 4.21% | 1.10 | 1.14 | 3.68% |
| S20x12-L16-P25 | 4.81% | 1.02 | 1.08 | 5.67% | 1.39 | 1.44 | 3.70% |
| S20x12-L16-P27 | 4.70% | 0.98 | 1.04 | 5.59% | 1.30 | 1.35 | 3.57% |
| S20x12-L16-P29 | 4.63% | 0.94 | 1.00 | 5.50% | 1.22 | 1.26 | 3.46% |
| S20x12-L12-P25 | 5.14% | 1.20 | 1.25 | 3.84% | 1.61 | 1.67 | 3.71% |
| S20x12-L12-P27 | 5.02% | 1.15 | 1.20 | 3.87% | 1.49 | 1.55 | 3.57% |
| S20x12-L12-P29 | 4.93% | 1.10 | 1.15 | 3.86% | 1.39 | 1.44 | 3.44% |
| S16x9-L20-P25 | 4.14% | 0.97 | 1.02 | 4.87% | 1.46 | 1.52 | 3.91% |
| S16x9-L20-P27 | 4.04% | 0.94 | 1.00 | 5.31% | 1.37 | 1.42 | 3.76% |

| | | | | | | | |
|------------------------------|-------|------|------|-------|------|------|-------|
| S16x9-L20-P29 | 3.94% | 0.92 | 0.97 | 5.55% | 1.28 | 1.33 | 3.62% |
| S16x9-L16-P25 | 4.44% | 1.25 | 1.35 | 7.17% | 1.70 | 1.77 | 3.85% |
| S16x9-L16-P27 | 4.33% | 1.21 | 1.30 | 6.58% | 1.58 | 1.64 | 3.68% |
| S16x9-L16-P29 | 4.24% | 1.18 | 1.25 | 5.79% | 1.47 | 1.53 | 3.52% |
| S16x9-L12-P25 | 4.80% | 1.55 | 1.68 | 7.80% | 1.99 | 2.07 | 3.96% |
| S16x9-L12-P27 | 4.70% | 1.48 | 1.60 | 7.24% | 1.84 | 1.91 | 3.74% |
| S16x9-L12-P29 | 4.57% | 1.41 | 1.52 | 7.22% | 1.70 | 1.77 | 3.56% |
| S12x6-L20-P25 | 3.34% | 0.97 | 1.01 | 3.86% | 1.33 | 1.37 | 3.20% |
| S12x6-L20-P27 | 3.25% | 0.94 | 0.97 | 3.79% | 1.24 | 1.28 | 3.09% |
| S12x6-L20-P29 | 3.19% | 0.90 | 0.93 | 3.71% | 1.16 | 1.20 | 2.98% |
| S12x6-L16-P25 | 3.63% | 1.19 | 1.24 | 4.01% | 1.55 | 1.60 | 3.25% |
| S12x6-L16-P27 | 3.55% | 1.14 | 1.19 | 3.91% | 1.44 | 1.48 | 3.12% |
| S12x6-L16-P29 | 3.45% | 1.09 | 1.13 | 3.81% | 1.34 | 1.38 | 2.99% |
| S12x6-L12-P25 | 3.88% | 1.44 | 1.49 | 3.81% | 1.78 | 1.83 | 3.05% |
| S12x6-L12-P27 | 3.79% | 1.36 | 1.41 | 3.70% | 1.64 | 1.69 | 2.91% |
| S12x6-L12-P29 | 3.68% | 1.28 | 1.33 | 3.60% | 1.51 | 1.55 | 2.80% |
| S23.5x11.5-L5.25-P29 | 5.83% | 1.28 | 1.33 | 3.61% | 1.55 | 1.60 | 3.38% |
| S11x6-L19-P25 | 3.16% | 0.95 | 0.99 | 3.57% | 1.16 | 1.20 | 3.59% |
| S16x11-L21-P27 | 3.94% | 0.89 | 0.93 | 3.71% | 1.31 | 1.36 | 3.66% |
| S18x8.5-L1-P23 | 6.11% | 2.03 | 2.10 | 3.18% | 2.34 | 2.41 | 2.94% |
| S18.5x11.5-L12.75-P30 | 4.59% | 1.12 | 1.17 | 3.85% | 1.39 | 1.44 | 3.29% |

To determine the effect of walkway on the modal response, the differential percentage of the modal frequency was graphed over the walkway mass percentage of the system in Figure 3.1.1 for the torsional mode shape and in Figure 3.1.3 for the chopping mode shape. This data seems marginally uncorrelated but clear groupings of data points are shown. Figure 3.1.2 (torsional mode shape) and Figure 3.1.4 (chopping mode shape) display the same data in accordance to the models' sign size. Here, groupings of data are easily seen as all similar sign sizes resulted in grouped data points. Each sign size group, except the extreme models, show three sets of three points that make

three straight lines. Each line resembles a mast truss length and each dot on the line accounts for one of the three pole heights.




Figure 3.1.1 – Torsional Mode Natural Frequency Change by Walkway Mass Percentage




Figure 3.1.2 – Torsional Mode Natural Frequency Change Grouped by Sign Size




Figure 3.1.3 – Chopping Mode Natural Frequency Change by Walkway Mass Percentage




Figure 3.1.4 – Chopping Mode Natural Frequency Change Grouped by Sign Size

The following trends were identified using the data shown in Figure 3.1.2 and Figure 3.1.4, in conjunction with the data in Table 3.1.1:

- 1) A larger sign size, and subsequent structure, generally corresponded with a higher natural frequency.
- 2) The medium sign size COSS exhibited the largest average change in natural frequency with removal of the walkway, followed by large sign size, then by the extreme models, then by small sign size.

- 3) Larger mast truss lengths corresponded with lower natural frequencies when compared to shorter mast truss lengths; thus, a larger difference of natural frequency with the walkway removed.
- 4) Larger pole height corresponded with lower natural frequencies when compared to smaller pole heights; thus, a larger difference of natural frequency with the walkway removed.
- 5) Removal of the walkway always resulted in a higher natural frequency when compared to the case where the walkway was attached.

These trends were the same for both characteristic modes. Each of these trends was consistent with typical cantilever dynamic behavior. The average percent change observed after walkway removal was 5.06% for the torsional mode and 3.47% for the chopping mode.

3.2 Computation Fluid Dynamic Modeling Results

Pressures were extracted from the influential surfaces from the 18 CFD models and were then multiplied by respective areas to produce a time history of the applied force. The pressure output was given in absolute pressure, so a correction of 14.7 psi or 1 atm (101.4 kPa) was subtracted from each pressure value. The force applied to the Shape in the direction of flow is denoted here as the “X-Force”, and the force applied to the Shape normal to the direction of flow is denoted here as the “Y-Force”. The X-Force is the difference between the pressure at the sign face and the pressure behind the sign, shown as surfaces a) (sign face) and b) (back of sign), respectively in Figure 2.5.1.1. The resulting pressure behind the sign was negligible in every test. The Y-Force was taken as the sum of the pressures sustained on surfaces c) through h) in Figure 2.5.1.1 (surfaces g) and h) were ignored if the model did not have a walkway attachment). Each

force has been plotted against time, showing a comparison between the grate/no grate conditions. The X-Force is denoted in the figures ending in “a”, and the Y-Force is denoted in the figures ending in “b”. The results for the force time-histories are presented in Figures 3.2.1.a – 3.2.9.b.




Figure 3.2.1.a – X-Force on Large Sign at V=30 mph (13.4 m/s)




Figure 3.2.1.b – Y-Force on Large Sign at V=30 mph (13.4 m/s)




Figure 3.2.2.a – X-Force on Large Sign at V=61.2 mph (27.4 m/s)




Figure 3.2.2.b – Y-Force on Large Sign at V=61.2 mph (27.4 m/s)




Figure 3.2.3.a – X-Force on Large Sign at V=105mph (46.9 m/s)




Figure 3.2.3.b – Y-Force on Large Sign at V=105mph (46.9 m/s)




Figure 3.2.4.a – X-Force on Medium Sign at V=30 mph (13.4 m/s)




Figure 3.2.4.b – Y-Force on Medium Sign at V=30 mph (13.4 m/s)




Figure 3.2.5.a – X-Force on Medium Sign at V=61.2 mph (27.4 m/s)




Figure 3.2.5.b – Y-Force on Medium Sign at V=61.2 mph (27.4 m/s)




Figure 3.2.6.a – X-Force on Medium Sign at V=105mph (46.9 m/s)




Figure 3.2.6.b – Y-Force on Medium Sign at V=105mph (46.9 m/s)




Figure 3.2.7.a – X-Force on Small Sign at V=30 mph (13.4 m/s)




Figure 3.2.7.b – Y-Force on Small Sign at V=30 mph (13.4 m/s)




Figure 3.2.8.a – X-Force on Small Sign at V=61.2 mph (27.4 m/s)




Figure 3.2.8.b – Y-Force on Small Sign at V=61.2 mph (27.4 m/s)




Figure 3.2.9.a – X-Force on Small Sign at V=105mph (46.9 m/s)




Figure 3.2.9.b – Y-Force on Small Sign at V=105mph (46.9 m/s)

All the time history data exhibited identical shapes and were similar for both directions of loading. An initial spike in the load was recorded, where the peak corresponded with the time it took for the gust of wind to travel from the fluid domain inlet to the sign face. This spike was very pronounced in Figure 3.2.10.a and Figure 3.2.10.b, which normalizes the force on the sign for both pressure and time. Figure 3.2.10.a and Figure 3.2.10.b also show the variance in eddies and vortices behind the sign that affected the wind loading on the sign over time. Some models experienced a second, less intense and smoother peak in the load, followed by another decline. This second peak was more prevalent and more pronounced in the Y-force data. The load continued to decrease at a decreasing rate until it eventually reached a constant value for most models. For the Y-force, this constant value was close to zero. The time history data followed typical behavior for a boundary layer forming on a bluff body subjected to a constant wind load, hence the gradual decrease in load over time.

Differences in the time history data between the grate and no grate conditions were minor for almost all models, especially for the X-force data. There were greater differences between the two conditions for the Y-force, which contributes to wind induced vibration. The greatest

observable differences were in the following three models: 1) Medium Sign at V=61.2 mph (27.4 m/s) model (Figure 3.2.5.b), 2) Medium Sign at V=105 mph (46.9 m/s) model (Figure 3.2.6.b), and 3) Large Sign at V=105 mph (46.9 m/s) model (Figure 3.2.9.b).

All of the figures showing the X-forces include the theoretical value of force (F) and the theoretical value of force with a shape factor (F_z), as obtained by Equation 3.2.1 and Equation 3.2.2, respectively. The values for force were derived from pressures applied to a surface multiplied by the surface's area (A). Equation 3.2.1 is expanded from Equation 2.4.1.1. Note, density is denoted by ρ , wind speed is denoted by V , and the shape factor is denoted by C_d .

$$F = \frac{1}{2}\rho AV^2 \quad (3.2.1)$$

$$F_z = \frac{1}{2}C_d\rho AV^2 \quad (3.2.2)$$




Figure 3.2.10.a – Normalized X-Force Time History Data

All the X-force data was bounded by F and F_z for the initial gust. The data trended to F before ultimately dropping under the theoretical value as the model established a laminar solution. The constant, final values were about 95% of the respective theoretical value.




Figure 3.2.10.b – Normalized Y-Force Time History Data

Vortices and eddies were identified behind the sign shape. To study their interactions and how they might contribute to vortex shedding, time histories of the Y-component of velocity were extracted at discrete points behind each CFD model. Where the Y-component of velocity consistently changed magnitude in a harmonic manner, it could be inferred that there is heavy eddy interaction which causes vortex shedding. The Y-component of velocity was extracted at the centerlines of the sign's height and length, behind the sign shape starting at a distance of $0.5 \cdot (\text{Sign Height})$ and increasing in increments of $0.25 \cdot (\text{Sign Height})$, up to a distance of $3.0 \cdot (\text{Sign Height})$ for each CFD model. The time histories are shown in Appendix A1, and all of the CFD models exhibited insignificant eddy interaction.

The velocity profile under the sign face, in the wake of the walkway, was extracted as well. The profile was extracted as wind velocity data points across a 6-ft line beneath the sign face. The profile was captured at increments of 0.10s up to 0.50s, then 0.75s and 1.00s, and then continued every 0.50s until the time history ended. The profile was also captured when the wind gust hit the sign face (this value changed for each wind speed), and these profiles have been presented in

Appendix A2. These profiles show an influence of the walkway attachment, which slows the air directly in its wake. The air moving around the walkway travels slightly faster than the air with no walkway present, resulting in a similar amount of air flow moving beneath the sign.

3.3 Finite Element Modeling – Dynamic Loading

The loads discussed in Section 3.2 were applied to the influential surfaces of the finite element models. Time history data describing displacements and stresses were extracted from these models. The displacements were extracted from the top chord in the mast truss at the end of the cantilever, and stresses were extracted from both box-connections and at the pole base.

The displacements were recorded in two cardinal directions, Z and Y. Z-displacements, denoted as ΔU_Z , are the displacements associated with the torsional mode response, which was activated by the natural wind gusts. The mode shape is shown in Figure 2.2.1. Y-displacements, denoted as ΔU_Y , are displacements associated with the chopping mode response, which is activated by aeroelastic phenomena. The mode shape is shown in Figure 2.2.3. Z-displacements were found to be much larger than Y-displacements.

Stresses in the box connection between the pole and mast arm were extracted for bending about the Y-axis and about the Z-axis. Stresses caused by bending about the Y-axis, denoted as S_{33} , were associated with the torsional mode response. Stresses caused by bending about the Z-axis, denoted as S_{11} , were associated with the chopping mode response. The torsional stresses in the pole, denoted as S_{21} , were also extracted. The stresses considered are shown in Figure 3.3.1.

All stress and displacement data were recorded as time histories. To simplify the data to a single value for each time history response, the range of displacements and the absolute maximum stress values were determined. These values were compared between the cases with and without

the walkway attached, using a percent difference, with the case where the walkway was attached as the baseline. The percent change data for all critical loading demand cases are shown in Tables 3.3.1 – 3.3.3, organized by wind speed.




Figure 3.3.1 – Pertinent locations where stresses were computed

Table 3.3.1 – Percent Change in Loading Demands for V=30mph (13.4 m/s)

| Model | Displacements | | Top Chord | | Bottom Chord | | Pole |
|-----------------------|---------------|--------------|-----------|-------|--------------|-------|------|
| | ΔU_Z | ΔU_Y | S33 | S11 | S33 | S11 | S21 |
| S20x12-L20-P25 | -4% | -260% | -1% | -183% | -2% | -175% | -6% |
| S20x12-L20-P27 | -4% | -278% | 0% | -204% | -3% | -196% | -5% |
| S20x12-L20-P29 | -4% | -253% | 1% | -195% | -3% | -193% | -1% |
| S20x12-L16-P25 | -3% | -223% | -2% | -210% | -3% | -209% | -4% |

| | | | | | | | |
|-----------------------|-----|-------|-----|-------|-----|-------|-----|
| S20x12-L16-P27 | -3% | -233% | -1% | -202% | -4% | -198% | -1% |
| S20x12-L16-P29 | -3% | -239% | 0% | -210% | -4% | -195% | -1% |
| S20x12-L12-P25 | -6% | -237% | -2% | -174% | -5% | -192% | -7% |
| S20x12-L12-P27 | -4% | -194% | -2% | -150% | -4% | -154% | -4% |
| S20x12-L12-P29 | -5% | -191% | -1% | -145% | -4% | -171% | -6% |
| S16x9-L20-P25 | 3% | -12% | 0% | -58% | 0% | -58% | 2% |
| S16x9-L20-P27 | 2% | -16% | 0% | -55% | -1% | -56% | 4% |
| S16x9-L20-P29 | 1% | -6% | 1% | -31% | -1% | -33% | 3% |
| S16x9-L16-P25 | 1% | -30% | 0% | -62% | -1% | -64% | 2% |
| S16x9-L16-P27 | 1% | -17% | 0% | -43% | -1% | -49% | 3% |
| S16x9-L16-P29 | 1% | -12% | -1% | -26% | -1% | -31% | 2% |
| S16x9-L12-P25 | 0% | -27% | 0% | -49% | -1% | -46% | 1% |
| S16x9-L12-P27 | 0% | -24% | 0% | -36% | 0% | -38% | 2% |
| S16x9-L12-P29 | 1% | -42% | -1% | -32% | 0% | -46% | -1% |
| S12x6-L20-P25 | 2% | -37% | 0% | -39% | 1% | -43% | 5% |
| S12x6-L20-P27 | 2% | -30% | 0% | -24% | 1% | -30% | 4% |
| S12x6-L20-P29 | 2% | -36% | 0% | -28% | 1% | -36% | 1% |
| S12x6-L16-P25 | 1% | -22% | 1% | -27% | -1% | -31% | 4% |
| S12x6-L16-P27 | 1% | -29% | 1% | -23% | -1% | -25% | 2% |
| S12x6-L16-P29 | 1% | -41% | 1% | -19% | 1% | -29% | 1% |
| S12x6-L12-P25 | 1% | -37% | 2% | -24% | -1% | -28% | 0% |
| S12x6-L12-P27 | 2% | -26% | 2% | -37% | -2% | -38% | 2% |
| S12x6-L12-P29 | 0% | -27% | 1% | -8% | 1% | -15% | 2% |

Table 3.3.2 – Percent Change in Loading Demands for V=61.2 mph (27.4 m/s)

| Model | Displacements | | Top Chord | | Bottom Chord | | Pole |
|-----------------------|----------------------|--------------|------------------|------------|---------------------|------------|-------------|
| | ΔU_z | ΔU_y | S33 | S11 | S33 | S11 | S21 |
| S20x12-L20-P25 | 0% | -26% | 2% | -38% | 0% | -35% | -2% |
| S20x12-L20-P27 | 0% | -22% | 2% | -35% | 0% | -34% | 0% |
| S20x12-L20-P29 | 0% | -23% | 2% | -18% | -1% | -19% | 2% |

| | | | | | | | |
|-----------------------|-----|------|-----|-------|-----|-------|-----|
| S20x12-L16-P25 | 1% | -27% | 0% | -34% | 0% | -29% | -3% |
| S20x12-L16-P27 | 3% | -31% | 1% | -15% | -1% | -15% | 3% |
| S20x12-L16-P29 | 0% | -28% | 3% | -9% | -2% | -7% | 2% |
| S20x12-L12-P25 | -1% | -37% | 0% | -21% | -1% | -29% | -4% |
| S20x12-L12-P27 | 0% | -29% | 0% | -3% | -2% | -21% | 1% |
| S20x12-L12-P29 | -1% | -23% | 0% | -6% | -1% | -17% | -2% |
| S16x9-L20-P25 | 2% | -39% | 0% | -115% | -1% | -107% | 2% |
| S16x9-L20-P27 | 0% | -45% | -1% | -122% | -1% | -123% | 3% |
| S16x9-L20-P29 | 0% | -54% | -1% | -108% | -2% | -105% | 2% |
| S16x9-L16-P25 | 0% | -56% | 0% | -122% | -1% | -111% | 3% |
| S16x9-L16-P27 | 0% | -35% | -1% | -115% | -1% | -108% | 4% |
| S16x9-L16-P29 | 1% | -39% | -1% | -119% | -1% | -112% | 1% |
| S16x9-L12-P25 | -1% | -61% | 0% | -129% | -3% | -118% | 0% |
| S16x9-L12-P27 | -2% | -72% | -1% | -115% | -1% | -118% | 2% |
| S16x9-L12-P29 | -1% | -62% | -1% | -104% | -1% | -104% | 0% |
| S12x6-L20-P25 | 2% | -11% | 1% | -32% | 0% | -28% | 5% |
| S12x6-L20-P27 | 2% | -9% | 1% | -19% | 1% | -37% | 3% |
| S12x6-L20-P29 | 2% | -17% | 0% | -14% | 2% | -19% | 5% |
| S12x6-L16-P25 | 2% | -23% | 2% | -20% | 0% | -31% | 2% |
| S12x6-L16-P27 | 2% | -28% | 2% | -22% | -1% | -39% | 1% |
| S12x6-L16-P29 | 2% | -14% | 2% | -27% | 0% | -35% | -2% |
| S12x6-L12-P25 | 3% | -21% | 3% | -23% | 0% | -20% | 1% |
| S12x6-L12-P27 | 3% | -28% | 3% | -28% | -1% | -24% | 1% |
| S12x6-L12-P29 | 2% | -25% | 1% | -39% | -1% | -24% | 2% |

Table 3.3.3 – Percent Change in Loading Demands for V=105mph (46.9 m/s)

| Model | Displacements | | Top Chord | | Bottom Chord | | Pole |
|-----------------------|--------------------------------|--------------------------------|------------------|------------|---------------------|------------|-------------|
| | ΔU_Z | ΔU_Y | S33 | S11 | S33 | S11 | S21 |
| S20x12-L20-P25 | -3% | 26% | 0% | -27% | -1% | -22% | -4% |
| S20x12-L20-P27 | -3% | 18% | 0% | -18% | -2% | -20% | -3% |

| | | | | | | | |
|-----------------------|-----|------|-----|------|-----|------|-----|
| S20x12-L20-P29 | -3% | 13% | 1% | -15% | -2% | -15% | 1% |
| S20x12-L16-P25 | -3% | 27% | -1% | 2% | -1% | -1% | -3% |
| S20x12-L16-P27 | -3% | 28% | 0% | 9% | -2% | 5% | 2% |
| S20x12-L16-P29 | -3% | 21% | 0% | 7% | -2% | 0% | 0% |
| S20x12-L12-P25 | -1% | 25% | 0% | 14% | -2% | 15% | -3% |
| S20x12-L12-P27 | -1% | 29% | -1% | 20% | -2% | 20% | 2% |
| S20x12-L12-P29 | -2% | 31% | 0% | 22% | -2% | 24% | -1% |
| S16x9-L20-P25 | -1% | -12% | 0% | -39% | -1% | -33% | 2% |
| S16x9-L20-P27 | -1% | -7% | -1% | -35% | -1% | -46% | -1% |
| S16x9-L20-P29 | 0% | -8% | -1% | -38% | -2% | -35% | 2% |
| S16x9-L16-P25 | -1% | -43% | 0% | -51% | -1% | -47% | 3% |
| S16x9-L16-P27 | -1% | -44% | 0% | -53% | 0% | -54% | 2% |
| S16x9-L16-P29 | -2% | -25% | -1% | -48% | -1% | -32% | 2% |
| S16x9-L12-P25 | 0% | 15% | 0% | -27% | -1% | -32% | 0% |
| S16x9-L12-P27 | -2% | -3% | 0% | -31% | -1% | -36% | 1% |
| S16x9-L12-P29 | -2% | -24% | -1% | -40% | -1% | -48% | -1% |
| S12x6-L20-P25 | 2% | -1% | 1% | -39% | 0% | -28% | 5% |
| S12x6-L20-P27 | 2% | -10% | 1% | -33% | 1% | -28% | 3% |
| S12x6-L20-P29 | 1% | -12% | 0% | -16% | 2% | -23% | 2% |
| S12x6-L16-P25 | 3% | 7% | 2% | -35% | 0% | -38% | 5% |
| S12x6-L16-P27 | 2% | -8% | 2% | -37% | 0% | -40% | 6% |
| S12x6-L16-P29 | 3% | -11% | 2% | -38% | -1% | -39% | -2% |
| S12x6-L12-P25 | 3% | -12% | 3% | -76% | 0% | -35% | 3% |
| S12x6-L12-P27 | 4% | -10% | 2% | -77% | 1% | -30% | 1% |
| S12x6-L12-P29 | 3% | -21% | 2% | -62% | -1% | -32% | 7% |

Trends from both characteristic modes were identified from the values reported in Tables 3.3.1 through 3.3.3:

- 1) Removal of the walkway had a minimal effect on responses in the torsional mode, including displacements and stresses in both the box-connection and the pole. The maximum increase in ΔU_Z displacement was 4%. The maximum increase in bending stress in the box-connection under this mode (S33) was 3%. The maximum torsional stress increase (S21) was 7%.
- 2) Removal of the walkway decreased, and in some cases greatly decreased, displacements and stresses affected in the chopping mode in all sign structures at all wind speeds, except the large sign structures with an applied wind speed of 105 mph (46.9 m/s). This latter behavior was caused by a second distinct peak in the applied Y-Force shown in Figure 3.2.3.b at approximately 0.75 seconds. This increased the ΔU_Y displacement by a maximum of 31%, and increased the bending stress in the box-connection (S11) by a maximum of 24%, both occurring in model S20x12-L12-P29.

Values extracted for stress and displacement can found in section A3 in the Appendix.

3.4 Experimental Results

Force data was recorded for a scaled model sign shape subjected to experimental wind gusts in a wind tunnel using a series of load cells. Seven different wind speeds were used, with a maximum wind speed of 40 mph (17.9 m/s) and a minimum wind speed of 10 mph (4.5 m/s). The wind speed was changed in increments of 5 mph (2.2 m/s). Data was recorded three times for each wind speed, and the average response was calculated. Since the scaled model was a relatively large shape as compared to the cross-section of the wind tunnel, the force applied by the wind was

artificially smaller due to the blockage effect (Sahini 2004). Corrected values were determined by multiplying the average force at each wind speed by the blockage correction factor (Ψ), defined by Equation 3.4.1:

$$\Psi = 1 + \phi C_d \frac{A_m}{A_w} \quad (3.4.1)$$

Variables for the blockage correction factor have been defined in Table 3.4.1. The blockage ratio (ϕ) is defined by Equation 3.4.2, where the height of the model is denoted by (h) and the height of the cross-sectional testing area is defined by (H).

$$\phi = h/H \quad (3.4.2)$$

Table 3.4.1 – Blockage Correction Factor (Shaini 2004)

| Variable | Notation | Value | | Units (S.I) |
|-----------------------------------|----------|----------------|----------------|-----------------------------------|
| | | w/ Walkway | w/o Walkway | |
| Model Height | h | 1.969 (0.600) | 1.688 (0.515) | ft (m) |
| Wind Tunnel Height | H | 3.00 (0.914) | 3.00 (0.914) | ft (m) |
| Blockage Ratio | ϕ | 0.6563 | 0.5625 | - |
| Shape Factor | C_d | 1.18 | 1.18 | - |
| Model Area | A_m | 5.063 (0.4703) | 5.063 (0.4703) | ft ² (m ²) |
| Wind Tunnel Area | A_w | 12.00 (1.115) | 12.00 (1.115) | ft ² (m ²) |
| Blockage Correction Factor | Ψ | 1.33 | 1.28 | - |

Figure 3.4.1 shows the measured forces behind the sign for the different wind speeds. Upper and lower theoretical bounds (Equation 3.2.1 and Equation 3.2.2) have also been included in the plot.

The measured forces corresponded well with the predicted range. Wind speeds between 20 mph (8.9 m/s) and 40 mph (17.9 m/s) produced forces that fell between the theoretical bounds, while the 10 mph (4.5 m/s) and 15 mph (6.7 m/s) produced measured forces that fell just under the lower theoretical bound, Equation 3.2.1. Overall, the walkway was found to have a minimal effect

on the forces measured under wind loading, with removal of the walkway tending to result in slightly lower forces behind the sign.

To compare to the physical measurements against the CFD-derived data, the peak force values from each CFD model at 30 mph (13.4 m/s) and the experimental results were normalized by area to yield the pressure applied to the sign conveyed in Table 3.4.2.




Figure 3.4.1 – Experimental Loading Data

Table 3.4.2 – Applied Pressure to CFD Models and Scale Model at V=30 mph (13.4 m/s)

| Sign Size | w/ Walkway | w/o Walkway |
|--------------|--------------|--------------|
| | psf (Pa) | psf (Pa) |
| Small | 2.66 (127.4) | 2.63 (125.9) |
| Medium | 2.66 (127.4) | 2.70 (129.3) |
| Large | 2.55 (122.1) | 2.53 (121.1) |
| Experimental | 2.56 (122.6) | 2.45 (117.3) |

Overall, the applied wind loading pressures from the CFD models and the experimental testing were similar, with the largest difference being 10%. The presence of a walkway attachment did not significant change the force response of the sign shape.

Turbulence created by wind loading on the sign shape and the walkway in the experimental testing was studied using a fog and laser technique. Laser planes at the sign face and behind the sign showed the largest change and the greatest turbulence when compared to the laser plane in front of the sign face. Figure 3.4.2 and Figure 3.4.3 show the turbulence with the walkway attachment in place, and Figure 3.4.4 and Figure 3.4.5 show the turbulence without the walkway attachment in place.




Figure 3.4.2 – Laser plane behind scale model




Figure 3.4.3 – Laser plane at sign face





Figure 3.4.4 – Laser plane behind scale model **Figure 3.4.5** – Laser plane at sign face

This technique indicated that the walkway itself produced turbulent flow, which can affect the downstream sign shape. The eddies and vortices in the wake of the sign developed over a greater distance below the sign shape when the walkway attachment was present.

CHAPTER 4 – CONCLUSIONS AND RECOMMENDATIONS

In this chapter, conclusions are offered based on results presented in the previous chapter. These are organized by how the dynamic properties change (Section 4.1) and how the aerodynamic shape and subsequent forces on the sign shape changed (Section 4.2). Suggestions for future work are also offered in this chapter.

4.1 Conclusions Regarding Changes to Dynamic Properties with Walkway Removal

Analyzing the results of the fundamental frequencies for both characteristic mode shapes has led to multiple conclusions regarding two-chord COSS dynamic properties, and the effect that the presence of a walkway attachment has on them:

- 1) Removal of the walkway always resulted in a higher natural frequency for COSS with an average of 5.09% increase in the torsional mode and 3.47% increase in the chopping mode.
- 2) Variable design characteristics, such as: sign size, mast arm length, and pole height had a greater effect on both fundamental natural frequencies than did the presence of a walkway.
- 3) The torsional mode shape always exhibited a lower natural frequency than the chopping mode shape.
- 4) The torsional mode natural frequency exhibited more variability across models with the removal of the walkway, especially in medium sign sized COSS systems.
- 5) The maximum differential percentage for the torsional mode natural frequency was 7.8%, for model S16x9-L12-P25, with the average resulting in 4.7% change.
- 6) The maximum differential percentage for the chopping mode natural frequency was 5.1%, for model S20x12-L20-P25, with the average resulting in 3.5% change.
- 7) The walkway had little to no effect on the damping ratio for the COSS studied.

- 8) The walkway did not significantly change the dynamic properties of two-chord COSS systems.

Comparing and contrasting the data in Table 3.1.1, sign size was found to have the greatest influence on the dynamic properties of two-chord COSS. This is because member sizes and spacing are dependent on the size of the sign the members are supporting. It is important to note that there are not three sign sizes on similar structures, but rather three sign sizes on *three different supporting structures*. After sign size, the mast truss length had the second greatest effect on the dynamic properties, followed by the pole length.

4.2 Conclusions Regarding Changes to Aerodynamic Shape and Loading Conditions

Examination of the results from the CFD and dynamically-loaded structural models has led to the following conclusions on how the walkway attachment changes the aerodynamic shape:

- 1) The walkway did not deflect wind away from the sign, and wind loading on the sign shape was equivalent with or without the walkway attachment present.
- 2) Wind loading in the experimental testing and CFD models produced similar pressures for a wind speed of 30 mph (13.4 m/s) (the common wind speed between the two modalities), with a 10% maximum difference.
- 3) The Y-component of the velocity did not appear to change in a manner that would be consistent with vortex shedding and/or galloping based off the data in Appendix A1.
- 4) Removal of the walkway did not significantly change or increase the stresses in the box-connection or the pole, with an average change of -0.3% in S33 stresses, -55% in S11 stresses, and 0.8% in S21 stresses.
- 5) Removal of the walkway did not significantly change the aerodynamic shape.

Expanding on these, it appears that the walkway does not significantly act as a diffuser to disrupt eddy interaction simply due to its placement on the sign structure. The walkway causes its own turbulence which can negatively affect the succeeding sign shape. Ultimately, the walkway attachment was found to have a very minimal effect on the load the sign structure experiences from natural wind gusts, the aeroelastic phenomena produced in the wake of the sign structure, and displacements and stresses developed by the natural wind gusts.

4.3 Future Work

The following suggestions are offered for future work, to improve the state-of-the-art around analyzing and designing COSS:

- 1) Development of fluid-structure interaction models with deformable fluid domains for more accurate analytical models.
- 2) Deployment of instruments such as accelerators and anemometers in the field on constructed COSS, to develop an improved understanding of how different wind loading scenarios affect sign structures.
- 3) Additional wind tunnel testing with differently sized sign shapes to develop an improved understanding of how walkway removal affects sign shapes of all sizes and to further validate CFD modeling techniques.
- 4) Extension of these methods to other COSS construction types.

REFERENCES

- American Association of State Highway and Transportation Officials (AASHTO) (2001). *Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals*, 4th Edition. With Interims, Washington, D.C.
- American Association of State Highway and Transportation Officials (AASHTO) (2004). *LRFD Bridge Design Specifications*, 3rd Edition. With Interims, Washington, D.C.
- American Association of State Highway and Transportation Officials (AASHTO) (2015a). *LRFD Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals*, 1st Edition. With Interims, Washington, D.C.
- American Association of State Highway and Transportation Officials (AASHTO) (2015b). *AASHTO LRFD Bridge Design Specifications*, 7th Edition. With Interims, Washington, D.C.
- American Society for Metals (ASM) International Handbook Committee (1990). *Metals Handbook*: Vol. 2, Properties and Selection–Nonferrous Alloys and Pure Metals: ASM International Handbook. New York, NY.
- American Society for Testing and Materials (ASTM) “ASTM Standard A709/A709M-18.” (2018). *Standard Specification for Structural Steel for Bridge*: ASTM International. West Conshohocken, PA.
- American Society of Civil Engineers (ASCE) (2010). *ASCE 7-10: Minimum Design Loads for Buildings and Other Structures*. With Interims, Washington, D.C.
- Barlow, J. B., Rae Jr., W. H., and Pope, A. (1999). “Low-Speed Wind Tunnel Testing.” John Wiley & Sons, Inc., New York, NY.
- Beneberu, E., Goode, J., and Yazdani, N. (2014). “Computational Fluid Dynamics Application for Design of Highway Sign Support Structures.” *International Journal of Civil and Structural Engineering*, 5(2), 101-111.
- Chao, S., Jiao, C., and Liu, S. (2016). “Research on Feasibility of Computational Fluid Dynamics (CFD) Method for Traffic Signs Board Calculation.” Paper presented at the IOP Conference Series: Earth and Environmental Science.

- Cheung, J. O., and Liu, C.H. (2011). “CFD Simulations of Natural Ventilation Behaviour in High-Rise Buildings in Regular and Staggered Arrangements at Various Spacings.” *Energy and Buildings*, 43(5), 1149-1158.
- Constantinescu, G., Bhatti, A., and Tokyay, T. (2008). “A Numerical Study of Wind Loads on Large Highway Sign Structures.” Paper presented at the 18th Structures Congress 2008: Analysis and Computation Specialty Conference.
- Craig, R. R., and Kurdila, A. J. (2006). *Fundamentals of Structural Dynamics*: John Wiley & Sons. Hoboken, NJ.
- Creamer, B.M., Frank, K.H. and Klinger, R.E. (1979). “Fatigue Loading of Cantilever Sign Structures from Truck Wind Gusts.” Research Report 209-1F, Project 3-5-77-209, Center for Highway Research, The University of Texas, Austin, TX.
- Dassault Systèmes Simulia (DSS) (2014). “Abaqus FEA Version 6.14.” Dassault Systèmes Simulia Corp.
- DSS (2015). “Abaqus/CAE User's Guide.” Dassault Systèmes Simulia Corp.
- Dexter, R.J. and Johns, K.W. (2005). “The Development of Fatigue Design Load Ranges for Cantilevered Sign and Signal Support Structures.” *Journal of Wind Engineering*, 77, 315-325.
- Dexter, R.J. and Ricker, M.J. (2002). “Fatigue Resistant Design of Cantilevered Signal, Sign and Light Supports.” NCHRP Report 469, Transportation Research Board, Washington, D.C.
- Dowling, N. E. (1999). *Mechanical Behavior of Materials*: Engineering Methods for Deformation, Fracture, and Fatigue, 2nd Edition: Prentice-Hall, Inc., Upper Saddle River, NJ.
- Fouad, F.H., Davidson, J.S., and Delatte, N. (2003). “Structural Supports for Highway Signs, Luminaires, and Traffic Signals.” NCHRP Report 494, Transportation Research Board, Washington, D.C.
- Gallow, M. S. (2014). “Mitigating Fatigue of Cantilevered Overhead Sign Structures Due to Natural and Truck-Induced Wind Gusts.” MS thesis, The University of Alabama at Birmingham, Birmingham, AL.

- Gallow, M. S., Fouad, F. H., and Hosch, I. E. (2015). "Mitigating Fatigue in Cantilevered Overhead Sign Structures." *Transportation Research Record: Journal of the Transportation Research Board*, No. 2522, 18-26.
- Gemba, K. (2007). "Measurement of Boundary Layer on a Flat Plate." California State University, Long Beach, experimental report.
- Gilani, A., and Whittaker, A. (2000). Fatigue-Life Evaluation of Steel Post Structures. II: Experimentation. *Journal of Structural Engineering*, 126(3), 331-340.
- Ginal, S. (2003). "Fatigue Performance of Full-Span Sign Support Structures Considering Truck-Induced Gust and Natural Wind Pressures." MSCE thesis, Marquette University, Milwaukee, WI.
- Hall, N. (Ed.). (2015). "Air Properties Definitions." Glenn Research Center, Nation Aeronautics and Space Administration (NASA). Cleveland, OH. Retrieved from: <https://www.grc.nasa.gov/www/k-12/airplane/airprop.html>.
- Holmes, J. D. (2007). "Wind Loading of Structures." Taylor & Francis, New York, NY.
- Hong, H. P., Zu, G. G., and King, J. P. C. (2016). "Estimating Fatigue Design Load for Overhead Steel Sign Support Structures Under Truck-Induced Wind Pressure." *Canadian Journal of Civil Engineering*, 43(3), 279-286.
- Hosch, I. E. (2009). "Design of Highway Overhead Cantilever-Type Sign Support Structures for Fatigue Loads." Ph.D Dissertation, The University of Alabama at Birmingham, Birmingham, AL.
- Johns, K. W., and Dexter, R. J. (1998a). "The Development of Fatigue Design Load Ranges for Cantilevered Sign and Signal Support Structures." *Journal of Wind Engineering and Industrial Aerodynamics*, 77, 315-326.
- Kacin, J. A. (2009). "Fatigue Life Estimation of a Highway Sign Structure." MS thesis, University of Pittsburgh, Pittsburgh, PA.
- Kaczinski, M.R., Dexter, R.J. and Van Dien, J.P. (1998). "Fatigue Design of Cantilevered Signal, Sign, and Light Supports." NCHRP Report 412, Transportation Research Board, Washington, D.C.


- Kadoya, K., Matsunaga, N., and Nagashima, A. (1985). "Viscosity and Thermal Conductivity of Dry Air in the Gaseous Phase." *Journal of Physical and Chemical Reference Data*, 14(4), 947-970.
- Kuhl, E., Hulshoff, S., and De Borst, R. (2003). "An Arbitrary Lagrangian Eulerian Finite-Element Approach for Fluid-Structure Interaction Phenomena." *International Journal for Numerical Methods in Engineering*, 57(1), 117-142.
- Kwon, H.b., Park, Y.W., Lee, D.h., and Kim, M.S. (2001). "Wind tunnel experiments on Korean high-speed trains using various ground simulation techniques." *Journal of Wind Engineering and Industrial Aerodynamics*, 89(13), 1179-1195.
- Louisiana Department of Transportation and Development (La DOTD). (2016). The DOTD Sign Shop, YouTube. Retrieved from: <https://www.youtube.com/watch?v=8i0qaekBs3Q>.
- Li, X., Whalen, T., and Bowman, M. (2006). "Fatigue Strength and Evaluation of Sign Structures." West Lafayette, IN.
- Li, X., Whalen, T., and Bowman, M. (2005). "Fatigue Strength and Evaluation of Double-Mast Arm Cantilevered Sign Structures." *Transportation Research Record: Journal of the Transportation Research Board*, No. 1928, 64-72.
- Mangat, J. (2012). Global News, YouTube. Retrieved from: https://www.youtube.com/watch?time_continue=3&v=rbtoeiP6Jwo.
- McDonald, J. R., Mehta, K., and Oler, W. (1995). "Wind Load Effects on Signs, Luminaires, and Traffic Signal Structures." Texas Department of Transportation. Austin, TX.
- Montazeri, H., and Blocken, B. (2013). "CFD Simulation of Wind-Induced Pressure Coefficients on Buildings with and without Balconies: Validation and Sensitivity Analysis." *Building and Environment*, 60, 137-149.
- Puckett, J., Garlich, M., and Nowak, A. (2014). "Development and Calibration of AASHTO LRFD Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals." NCHRP Report 796, Transportation Research Board, Washington, D.C.

- Rice, J. A., LaFave, M. L., and Mehuys, C. H. (2008) "End Connection Effects on Vortex Shedding Susceptibility of Welded Aluminum Truss Tubular Web Members." *Journal of Performance of Constructed Facilities*, 22(5).
- Rizzo, P., and Zhu, X. (2010). "Sensing Technology for Damage Assessment of Sign Supports and Cantilever Poles." Pennsylvania Department of Transportation. Pittsburgh, PA.
- Sahini, D. (2004). "Wind Tunnel Blockage Corrections: A Computational Study." MS thesis, Texas Tech University, Lubbock, TX.
- Santiago, J. L., et al. (2007). "CFD Simulation of Airflow over a Regular Array of Cubes. Part I: Three-Dimensional Simulation of the Flow and Validation with Wind-Tunnel Measurements." *Boundary-Layer Meteorology*, 122(3), 609-634.
- Sváček, P. (2017). "Numerical Simulation of Fluid-Structure Interactions with Stabilized Finite Element Method." *Advances in Engineering Software*, 113, 96-107.
- Tian, F. B., Dai, H., and Luo, H. (2014). "Fluid-Structure Interaction Involving Large Deformations: 3D Simulations and Applications to Biological Systems." *Journal of Computational Physics*, 258, 451-469.
- Voss, D. (2016) "This Month in Physics History: November 7, 1940: Collapse of the Tacoma Narrows Bridge." American Physical Society, 25(10). Ridge, NY.
- Yarusevych, S., Sullivan, P., and Kawall J. G. (2009). "On vortex shedding from airfoil in low-Reynolds-number flows." *Journal of Fluid Mechanics*, 632, 245-271.
- Zuo, D. and Letchford, C. W. (2010). "Wind-Induced Vibration of a Traffic-Signal-Support Structure with Cantilevered Tapered Circular Mast Arm." *Engineering Structures*, 32(10), 3171-3179.
- Zuo, D., Smith, D., and Mehta, K. (2012). "Benchmark Wind Tunnel Study of Wind Loading on Rectangular Sign Structures." Wind Science and Engineering Research Center, Texas Tech University. Lubbock, TX.


APPENDIX A1

A1.1 – Y-Component of Velocity Behind Large Sign at V=30 mph (13.4 m/s)


Y-Component of Velocity at 0.50h Behind Sign









Y-Component of Velocity at 0.75h Behind Sign





Y-Component of Velocity at 1.00h Behind Sign











*Velocity scales are different from the rest of the batch.

A1.2 – Y-Component of Velocity Behind Large Sign at V=61.2 mph (27.4 m/s)


Y-Component of Velocity at 0.50h Behind Sign









Y-Component of Velocity at 0.75h Behind Sign





Y-Component of Velocity at 1.00h Behind Sign











A1.3 – Y-Component of Velocity Behind Large Sign at V=105mph (46.9 m/s)


Y-Component of Velocity at 0.50h Behind Sign









Y-Component of Velocity at 0.75h Behind Sign





Y-Component of Velocity at 1.00h Behind Sign











A1.4 – Y-Component of Velocity Behind Medium Sign at V=30 mph (13.4 m/s)


Y-Component of Velocity at 0.50h Behind Sign









Y-Component of Velocity at 0.75h Behind Sign





Y-Component of Velocity at 1.00h Behind Sign











A1.5 – Y-Component of Velocity Behind Medium Sign at V=61.2 mph (27.4 m/s)


Y-Component of Velocity at 0.50h Behind Sign









Y-Component of Velocity at 0.75h Behind Sign





Y-Component of Velocity at 1.00h Behind Sign




















A1.6 – Y-Component of Velocity Behind Medium Sign at V=105mph (46.9 m/s)











A1.7 – Y-Component of Velocity Behind Small Sign at V=30 mph (13.4 m/s)


Y-Component of Velocity at 0.50h Behind Sign









Y-Component of Velocity at 0.75h Behind Sign





Y-Component of Velocity at 1.00h Behind Sign




















A1.8 – Y-Component of Velocity Behind Small Sign at V=61.2 mph (27.4 m/s)




















A1.9 – Y-Component of Velocity Behind Small Sign at V=105mph (46.9 m/s)



















APPENDIX A2










A2.1 – Large Sign Velocity Profile at V=30 mph (13.4 m/s)








A2.2 – Large Sign Velocity Profile at $V=61.2$ mph (27.4 m/s)








A2.3 – Large Sign Velocity Profile at V=105mph (46.9 m/s)

















A2.4 – Medium Sign Velocity Profile at V=30 mph (13.4 m/s)






*Wind speed scales are different from the rest of the batch.














A2.5 – Medium Sign Velocity Profile at V=61.2 mph (27.4 m/s)






*Wind speed scales are different from the rest of the batch.













A2.6 – Medium Sign Velocity Profile at V=105mph (46.9 m/s)






*Wind speed scales are different from the rest of the batch.

















A2.7 – Small Sign Velocity Profile at V=30 mph (13.4 m/s)















*Wind speed scales are different from the rest of the batch.








A2.8 – Small Sign Velocity Profile at V=61.2 mph (27.4 m/s)













A2.9 – Small Sign Velocity Profile at V=105mph (46.9 m/s)



*Wind speed scales are different from the rest of the batch.



APPENDIX A3

Table A3.1.1 – Displacements at V=30 mph (13.4 m/s)

| Model | ΔUZ | | | | ΔUY | | | |
|----------------|-------------|--------|-------------|--------|-------------|------|-------------|------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | in. | mm | in. | mm | in. | mm | in. | mm |
| S20x12-L20-P25 | 5.13 | 130.38 | 4.96 | 125.91 | 0.13 | 3.26 | 0.04 | 0.90 |
| S20x12-L20-P27 | 5.47 | 139.06 | 5.29 | 134.33 | 0.14 | 3.44 | 0.04 | 0.91 |
| S20x12-L20-P29 | 5.88 | 149.40 | 5.64 | 143.31 | 0.14 | 3.65 | 0.04 | 1.04 |
| S20x12-L16-P25 | 3.88 | 98.67 | 3.76 | 95.43 | 0.10 | 2.64 | 0.03 | 0.82 |
| S20x12-L16-P27 | 4.15 | 105.51 | 4.05 | 102.90 | 0.11 | 2.81 | 0.03 | 0.84 |
| S20x12-L16-P29 | 4.46 | 113.24 | 4.31 | 109.51 | 0.11 | 2.91 | 0.03 | 0.86 |
| S20x12-L12-P25 | 2.88 | 73.23 | 2.72 | 69.18 | 0.07 | 1.77 | 0.02 | 0.52 |
| S20x12-L12-P27 | 3.12 | 79.37 | 2.99 | 75.96 | 0.08 | 2.03 | 0.03 | 0.69 |
| S20x12-L12-P29 | 3.40 | 86.24 | 3.23 | 82.09 | 0.09 | 2.41 | 0.03 | 0.83 |
| S16x9-L20-P25 | 3.44 | 87.29 | 3.54 | 89.81 | 0.05 | 1.36 | 0.05 | 1.21 |
| S16x9-L20-P27 | 3.65 | 92.68 | 3.72 | 94.52 | 0.05 | 1.39 | 0.05 | 1.20 |
| S16x9-L20-P29 | 3.90 | 98.98 | 3.95 | 100.39 | 0.06 | 1.46 | 0.05 | 1.37 |
| S16x9-L16-P25 | 2.52 | 63.95 | 2.53 | 64.37 | 0.04 | 1.08 | 0.03 | 0.83 |
| S16x9-L16-P27 | 2.70 | 68.52 | 2.73 | 69.23 | 0.05 | 1.24 | 0.04 | 1.06 |
| S16x9-L16-P29 | 2.89 | 73.48 | 2.91 | 73.96 | 0.05 | 1.38 | 0.05 | 1.24 |
| S16x9-L12-P25 | 1.71 | 43.31 | 1.71 | 43.36 | 0.03 | 0.69 | 0.02 | 0.54 |
| S16x9-L12-P27 | 1.87 | 47.39 | 1.87 | 47.57 | 0.03 | 0.89 | 0.03 | 0.72 |
| S16x9-L12-P29 | 2.03 | 51.51 | 2.04 | 51.83 | 0.05 | 1.17 | 0.03 | 0.82 |
| S12x6-L20-P25 | 2.08 | 52.88 | 2.13 | 54.22 | 0.04 | 0.92 | 0.03 | 0.67 |
| S12x6-L20-P27 | 2.23 | 56.53 | 2.27 | 57.60 | 0.04 | 1.09 | 0.03 | 0.84 |
| S12x6-L20-P29 | 2.38 | 60.35 | 2.42 | 61.42 | 0.05 | 1.24 | 0.04 | 0.91 |
| S12x6-L16-P25 | 1.46 | 36.97 | 1.47 | 37.35 | 0.03 | 0.68 | 0.02 | 0.56 |
| S12x6-L16-P27 | 1.58 | 40.22 | 1.60 | 40.75 | 0.03 | 0.79 | 0.02 | 0.61 |
| S12x6-L16-P29 | 1.74 | 44.13 | 1.75 | 44.36 | 0.04 | 0.91 | 0.03 | 0.65 |
| S12x6-L12-P25 | 0.97 | 24.54 | 0.97 | 24.74 | 0.02 | 0.58 | 0.02 | 0.42 |
| S12x6-L12-P27 | 1.07 | 27.23 | 1.09 | 27.68 | 0.02 | 0.60 | 0.02 | 0.48 |
| S12x6-L12-P29 | 1.20 | 30.41 | 1.19 | 30.33 | 0.03 | 0.66 | 0.02 | 0.52 |

Table A3.1.2 – Top Box-Connection Stresses at V=30 mph (13.4 m/s)

| Model | S33 | | | | S11 | | | |
|----------------|------------|-------|-------------|-------|------------|------|-------------|------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 3.91 | 26.98 | 3.89 | 26.82 | 0.09 | 0.65 | 0.03 | 0.23 |
| S20x12-L20-P27 | 3.92 | 27.04 | 3.91 | 26.96 | 0.07 | 0.50 | 0.02 | 0.17 |
| S20x12-L20-P29 | 3.91 | 26.95 | 3.93 | 27.11 | 0.06 | 0.43 | 0.02 | 0.14 |
| S20x12-L16-P25 | 3.41 | 23.54 | 3.34 | 23.03 | 0.06 | 0.43 | 0.02 | 0.14 |
| S20x12-L16-P27 | 3.41 | 23.53 | 3.37 | 23.23 | 0.05 | 0.35 | 0.02 | 0.11 |
| S20x12-L16-P29 | 3.40 | 23.46 | 3.39 | 23.38 | 0.05 | 0.31 | 0.01 | 0.10 |
| S20x12-L12-P25 | 2.89 | 19.93 | 2.83 | 19.54 | 0.04 | 0.26 | 0.01 | 0.10 |
| S20x12-L12-P27 | 2.88 | 19.82 | 2.81 | 19.39 | 0.04 | 0.26 | 0.02 | 0.11 |
| S20x12-L12-P29 | 2.88 | 19.88 | 2.85 | 19.64 | 0.04 | 0.25 | 0.01 | 0.10 |
| S16x9-L20-P25 | 4.17 | 28.78 | 4.19 | 28.91 | 0.05 | 0.37 | 0.03 | 0.23 |
| S16x9-L20-P27 | 4.19 | 28.87 | 4.18 | 28.84 | 0.04 | 0.25 | 0.02 | 0.16 |
| S16x9-L20-P29 | 4.17 | 28.72 | 4.21 | 29.05 | 0.03 | 0.21 | 0.02 | 0.16 |
| S16x9-L16-P25 | 3.58 | 24.71 | 3.60 | 24.81 | 0.03 | 0.23 | 0.02 | 0.14 |
| S16x9-L16-P27 | 3.59 | 24.74 | 3.58 | 24.66 | 0.03 | 0.18 | 0.02 | 0.12 |
| S16x9-L16-P29 | 3.57 | 24.65 | 3.55 | 24.48 | 0.03 | 0.18 | 0.02 | 0.14 |
| S16x9-L12-P25 | 2.96 | 20.38 | 2.96 | 20.40 | 0.02 | 0.15 | 0.01 | 0.10 |
| S16x9-L12-P27 | 2.96 | 20.42 | 2.95 | 20.35 | 0.02 | 0.15 | 0.02 | 0.11 |
| S16x9-L12-P29 | 2.96 | 20.40 | 2.93 | 20.21 | 0.02 | 0.14 | 0.02 | 0.11 |
| S12x6-L20-P25 | 2.02 | 13.93 | 2.02 | 13.95 | 0.01 | 0.08 | 0.01 | 0.06 |
| S12x6-L20-P27 | 2.01 | 13.86 | 2.01 | 13.85 | 0.01 | 0.08 | 0.01 | 0.06 |
| S12x6-L20-P29 | 2.00 | 13.80 | 1.99 | 13.73 | 0.01 | 0.07 | 0.01 | 0.06 |
| S12x6-L16-P25 | 1.68 | 11.60 | 1.71 | 11.76 | 0.01 | 0.06 | 0.01 | 0.05 |
| S12x6-L16-P27 | 1.69 | 11.67 | 1.72 | 11.83 | 0.01 | 0.06 | 0.01 | 0.05 |
| S12x6-L16-P29 | 1.70 | 11.71 | 1.72 | 11.84 | 0.01 | 0.06 | 0.01 | 0.05 |
| S12x6-L12-P25 | 1.34 | 9.25 | 1.37 | 9.45 | 0.01 | 0.05 | 0.01 | 0.04 |
| S12x6-L12-P27 | 1.37 | 9.42 | 1.39 | 9.58 | 0.01 | 0.05 | 0.01 | 0.04 |
| S12x6-L12-P29 | 1.38 | 9.53 | 1.39 | 9.60 | 0.01 | 0.04 | 0.01 | 0.04 |

Table A3.1.3 – Bottom Box-Connection Stresses at V=30 mph (13.4 m/s)

| Model | S33 | | | | S11 | | | |
|----------------|------------|-------|-------------|-------|------------|------|-------------|------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 5.67 | 39.11 | 5.56 | 38.37 | 0.16 | 1.10 | 0.06 | 0.40 |
| S20x12-L20-P27 | 5.70 | 39.28 | 5.55 | 38.26 | 0.12 | 0.84 | 0.04 | 0.28 |
| S20x12-L20-P29 | 5.70 | 39.31 | 5.52 | 38.05 | 0.10 | 0.71 | 0.04 | 0.24 |
| S20x12-L16-P25 | 4.98 | 34.37 | 4.84 | 33.38 | 0.11 | 0.77 | 0.04 | 0.25 |
| S20x12-L16-P27 | 5.02 | 34.61 | 4.83 | 33.33 | 0.09 | 0.62 | 0.03 | 0.21 |
| S20x12-L16-P29 | 5.02 | 34.63 | 4.81 | 33.17 | 0.08 | 0.55 | 0.03 | 0.19 |
| S20x12-L12-P25 | 4.29 | 29.60 | 4.11 | 28.32 | 0.07 | 0.50 | 0.03 | 0.17 |
| S20x12-L12-P27 | 4.30 | 29.67 | 4.15 | 28.63 | 0.07 | 0.48 | 0.03 | 0.19 |
| S20x12-L12-P29 | 4.28 | 29.51 | 4.10 | 28.24 | 0.07 | 0.49 | 0.03 | 0.18 |
| S16x9-L20-P25 | 5.23 | 36.04 | 5.22 | 35.96 | 0.09 | 0.63 | 0.06 | 0.40 |
| S16x9-L20-P27 | 5.24 | 36.13 | 5.20 | 35.87 | 0.06 | 0.43 | 0.04 | 0.28 |
| S16x9-L20-P29 | 5.23 | 36.07 | 5.18 | 35.69 | 0.05 | 0.36 | 0.04 | 0.27 |
| S16x9-L16-P25 | 4.47 | 30.79 | 4.43 | 30.52 | 0.06 | 0.44 | 0.04 | 0.27 |
| S16x9-L16-P27 | 4.48 | 30.91 | 4.44 | 30.61 | 0.07 | 0.50 | 0.05 | 0.34 |
| S16x9-L16-P29 | 4.49 | 30.98 | 4.45 | 30.71 | 0.05 | 0.34 | 0.04 | 0.26 |
| S16x9-L12-P25 | 3.65 | 25.17 | 3.62 | 24.93 | 0.04 | 0.30 | 0.03 | 0.20 |
| S16x9-L12-P27 | 3.68 | 25.38 | 3.67 | 25.29 | 0.06 | 0.42 | 0.04 | 0.31 |
| S16x9-L12-P29 | 3.72 | 25.68 | 3.71 | 25.60 | 0.04 | 0.29 | 0.03 | 0.20 |
| S12x6-L20-P25 | 2.40 | 16.58 | 2.43 | 16.77 | 0.02 | 0.14 | 0.01 | 0.10 |
| S12x6-L20-P27 | 2.41 | 16.60 | 2.44 | 16.81 | 0.02 | 0.15 | 0.02 | 0.11 |
| S12x6-L20-P29 | 2.41 | 16.62 | 2.45 | 16.86 | 0.02 | 0.14 | 0.01 | 0.10 |
| S12x6-L16-P25 | 2.06 | 14.18 | 2.04 | 14.06 | 0.02 | 0.13 | 0.01 | 0.10 |
| S12x6-L16-P27 | 2.05 | 14.13 | 2.02 | 13.93 | 0.02 | 0.14 | 0.02 | 0.11 |
| S12x6-L16-P29 | 2.03 | 13.99 | 2.05 | 14.15 | 0.02 | 0.12 | 0.01 | 0.09 |
| S12x6-L12-P25 | 1.68 | 11.60 | 1.67 | 11.50 | 0.02 | 0.12 | 0.01 | 0.09 |
| S12x6-L12-P27 | 1.68 | 11.60 | 1.66 | 11.41 | 0.02 | 0.11 | 0.01 | 0.08 |
| S12x6-L12-P29 | 1.67 | 11.49 | 1.68 | 11.57 | 0.01 | 0.09 | 0.01 | 0.08 |

Table A3.1.4 – Pole Stresses at V=30 mph (13.4 m/s)

| Model | S21 | | | |
|----------------|------------|-------|-------------|-------|
| | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 3.42 | 23.56 | 3.23 | 22.27 |
| S20x12-L20-P27 | 3.71 | 25.58 | 3.54 | 24.41 |
| S20x12-L20-P29 | 3.96 | 27.31 | 3.91 | 26.94 |
| S20x12-L16-P25 | 3.34 | 23.00 | 3.20 | 22.08 |
| S20x12-L16-P27 | 3.46 | 23.87 | 3.44 | 23.73 |
| S20x12-L16-P29 | 3.85 | 26.54 | 3.81 | 26.30 |
| S20x12-L12-P25 | 3.35 | 23.07 | 3.12 | 21.52 |
| S20x12-L12-P27 | 3.62 | 24.98 | 3.48 | 24.02 |
| S20x12-L12-P29 | 4.04 | 27.83 | 3.81 | 26.26 |
| S16x9-L20-P25 | 1.96 | 13.54 | 2.00 | 13.78 |
| S16x9-L20-P27 | 2.15 | 14.86 | 2.25 | 15.49 |
| S16x9-L20-P29 | 2.39 | 16.45 | 2.47 | 17.05 |
| S16x9-L16-P25 | 1.93 | 13.32 | 1.98 | 13.64 |
| S16x9-L16-P27 | 2.16 | 14.89 | 2.22 | 15.33 |
| S16x9-L16-P29 | 2.36 | 16.28 | 2.42 | 16.65 |
| S16x9-L12-P25 | 1.89 | 13.04 | 1.91 | 13.17 |
| S16x9-L12-P27 | 2.08 | 14.36 | 2.12 | 14.60 |
| S16x9-L12-P29 | 2.32 | 16.02 | 2.31 | 15.91 |
| S12x6-L20-P25 | 1.38 | 9.52 | 1.46 | 10.04 |
| S12x6-L20-P27 | 1.56 | 10.77 | 1.62 | 11.17 |
| S12x6-L20-P29 | 1.71 | 11.76 | 1.73 | 11.92 |
| S12x6-L16-P25 | 1.35 | 9.32 | 1.41 | 9.70 |
| S12x6-L16-P27 | 1.52 | 10.48 | 1.54 | 10.65 |
| S12x6-L16-P29 | 1.67 | 11.54 | 1.69 | 11.66 |
| S12x6-L12-P25 | 1.30 | 8.95 | 1.30 | 8.95 |
| S12x6-L12-P27 | 1.41 | 9.73 | 1.44 | 9.90 |
| S12x6-L12-P29 | 1.55 | 10.66 | 1.57 | 10.84 |

Table A3.2.1 – Displacements at V=61.2 mph (27.4 m/s)

| Model | ΔUZ | | | | ΔUY | | | |
|----------------|-------------|--------|-------------|--------|-------------|-------|-------------|-------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | in. | mm | in. | mm | in. | mm | in. | mm |
| S20x12-L20-P25 | 20.94 | 531.86 | 21.00 | 533.39 | 0.38 | 9.64 | 0.30 | 7.63 |
| S20x12-L20-P27 | 22.36 | 567.91 | 22.39 | 568.58 | 0.42 | 10.66 | 0.34 | 8.72 |
| S20x12-L20-P29 | 23.91 | 607.39 | 23.95 | 608.23 | 0.55 | 13.84 | 0.44 | 11.22 |
| S20x12-L16-P25 | 16.34 | 414.98 | 16.44 | 417.60 | 0.30 | 7.70 | 0.24 | 6.08 |
| S20x12-L16-P27 | 17.11 | 434.49 | 17.59 | 446.66 | 0.33 | 8.45 | 0.25 | 6.47 |
| S20x12-L16-P29 | 18.26 | 463.84 | 18.29 | 464.63 | 0.35 | 8.77 | 0.27 | 6.85 |
| S20x12-L12-P25 | 12.07 | 306.46 | 11.99 | 304.56 | 0.28 | 6.99 | 0.20 | 5.12 |
| S20x12-L12-P27 | 13.18 | 334.75 | 13.13 | 333.49 | 0.26 | 6.59 | 0.20 | 5.09 |
| S20x12-L12-P29 | 14.33 | 364.01 | 14.23 | 361.33 | 0.27 | 6.80 | 0.22 | 5.54 |
| S16x9-L20-P25 | 14.10 | 358.10 | 14.39 | 365.49 | 0.30 | 7.58 | 0.21 | 5.46 |
| S16x9-L20-P27 | 14.90 | 378.52 | 14.97 | 380.13 | 0.31 | 7.94 | 0.22 | 5.48 |
| S16x9-L20-P29 | 15.77 | 400.64 | 15.85 | 402.50 | 0.33 | 8.48 | 0.22 | 5.49 |
| S16x9-L16-P25 | 10.64 | 270.21 | 10.66 | 270.65 | 0.25 | 6.23 | 0.16 | 4.00 |
| S16x9-L16-P27 | 11.35 | 288.17 | 11.33 | 287.78 | 0.25 | 6.25 | 0.18 | 4.63 |
| S16x9-L16-P29 | 12.06 | 306.34 | 12.13 | 307.99 | 0.27 | 6.84 | 0.19 | 4.92 |
| S16x9-L12-P25 | 7.55 | 191.86 | 7.46 | 189.55 | 0.18 | 4.67 | 0.11 | 2.90 |
| S16x9-L12-P27 | 8.25 | 209.52 | 8.11 | 205.87 | 0.20 | 5.16 | 0.12 | 3.00 |
| S16x9-L12-P29 | 8.91 | 226.39 | 8.80 | 223.51 | 0.21 | 5.22 | 0.13 | 3.21 |
| S12x6-L20-P25 | 8.31 | 211.04 | 8.49 | 215.54 | 0.11 | 2.72 | 0.10 | 2.46 |
| S12x6-L20-P27 | 8.89 | 225.90 | 9.08 | 230.57 | 0.10 | 2.58 | 0.09 | 2.37 |
| S12x6-L20-P29 | 9.54 | 242.20 | 9.70 | 246.36 | 0.10 | 2.66 | 0.09 | 2.28 |
| S12x6-L16-P25 | 5.92 | 150.47 | 6.06 | 153.98 | 0.09 | 2.40 | 0.08 | 1.95 |
| S12x6-L16-P27 | 6.43 | 163.37 | 6.54 | 166.20 | 0.10 | 2.42 | 0.07 | 1.88 |
| S12x6-L16-P29 | 6.93 | 176.08 | 7.07 | 179.54 | 0.09 | 2.23 | 0.08 | 1.96 |
| S12x6-L12-P25 | 4.16 | 105.77 | 4.30 | 109.15 | 0.08 | 1.99 | 0.06 | 1.65 |
| S12x6-L12-P27 | 4.56 | 115.80 | 4.70 | 119.30 | 0.08 | 2.06 | 0.06 | 1.61 |
| S12x6-L12-P29 | 4.98 | 126.38 | 5.07 | 128.68 | 0.08 | 2.08 | 0.07 | 1.67 |

Table A3.2.2 – Top Box-Connection Stresses at V=61.2 mph (27.4 m/s)

| Model | S33 | | | | S11 | | | |
|----------------|------------|--------|-------------|--------|------------|------|-------------|------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 16.40 | 113.05 | 16.65 | 114.80 | 0.29 | 2.01 | 0.21 | 1.46 |
| S20x12-L20-P27 | 16.39 | 113.01 | 16.73 | 115.33 | 0.26 | 1.77 | 0.19 | 1.31 |
| S20x12-L20-P29 | 16.41 | 113.14 | 16.81 | 115.94 | 0.25 | 1.70 | 0.21 | 1.44 |
| S20x12-L16-P25 | 14.25 | 98.24 | 14.30 | 98.61 | 0.21 | 1.42 | 0.15 | 1.06 |
| S20x12-L16-P27 | 14.22 | 98.05 | 14.41 | 99.39 | 0.17 | 1.19 | 0.15 | 1.04 |
| S20x12-L16-P29 | 14.15 | 97.57 | 14.52 | 100.11 | 0.16 | 1.10 | 0.15 | 1.01 |
| S20x12-L12-P25 | 12.19 | 84.05 | 12.25 | 84.46 | 0.15 | 1.07 | 0.13 | 0.88 |
| S20x12-L12-P27 | 12.13 | 83.62 | 12.18 | 83.96 | 0.13 | 0.87 | 0.12 | 0.84 |
| S20x12-L12-P29 | 12.16 | 83.84 | 12.18 | 83.98 | 0.12 | 0.81 | 0.11 | 0.76 |
| S16x9-L20-P25 | 17.30 | 119.31 | 17.23 | 118.83 | 0.25 | 1.74 | 0.12 | 0.81 |
| S16x9-L20-P27 | 17.29 | 119.21 | 17.09 | 117.87 | 0.21 | 1.45 | 0.09 | 0.65 |
| S16x9-L20-P29 | 17.19 | 118.53 | 17.09 | 117.83 | 0.18 | 1.23 | 0.09 | 0.59 |
| S16x9-L16-P25 | 15.00 | 103.45 | 14.97 | 103.24 | 0.18 | 1.26 | 0.08 | 0.57 |
| S16x9-L16-P27 | 15.00 | 103.39 | 14.86 | 102.46 | 0.15 | 1.05 | 0.07 | 0.49 |
| S16x9-L16-P29 | 14.93 | 102.93 | 14.73 | 101.57 | 0.13 | 0.91 | 0.06 | 0.42 |
| S16x9-L12-P25 | 12.54 | 86.48 | 12.52 | 86.34 | 0.13 | 0.91 | 0.06 | 0.40 |
| S16x9-L12-P27 | 12.53 | 86.43 | 12.44 | 85.80 | 0.11 | 0.74 | 0.05 | 0.35 |
| S16x9-L12-P29 | 12.49 | 86.14 | 12.31 | 84.90 | 0.10 | 0.70 | 0.05 | 0.35 |
| S12x6-L20-P25 | 8.16 | 56.23 | 8.23 | 56.72 | 0.04 | 0.24 | 0.03 | 0.18 |
| S12x6-L20-P27 | 8.13 | 56.03 | 8.17 | 56.34 | 0.03 | 0.21 | 0.02 | 0.17 |
| S12x6-L20-P29 | 8.10 | 55.88 | 8.11 | 55.93 | 0.03 | 0.17 | 0.02 | 0.15 |
| S12x6-L16-P25 | 6.84 | 47.16 | 7.01 | 48.36 | 0.03 | 0.20 | 0.02 | 0.16 |
| S12x6-L16-P27 | 6.88 | 47.46 | 7.05 | 48.58 | 0.03 | 0.17 | 0.02 | 0.14 |
| S12x6-L16-P29 | 6.92 | 47.71 | 7.04 | 48.52 | 0.02 | 0.16 | 0.02 | 0.13 |
| S12x6-L12-P25 | 5.59 | 38.55 | 5.74 | 39.54 | 0.02 | 0.14 | 0.02 | 0.11 |
| S12x6-L12-P27 | 5.64 | 38.87 | 5.78 | 39.88 | 0.02 | 0.13 | 0.01 | 0.10 |
| S12x6-L12-P29 | 5.69 | 39.23 | 5.77 | 39.77 | 0.02 | 0.12 | 0.01 | 0.09 |

Table A3.2.3 – Bottom Box-Connection Stresses at V=61.2 mph (27.4 m/s)

| Model | S33 | | | | S11 | | | |
|----------------|------------|--------|-------------|--------|------------|------|-------------|------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 23.84 | 164.35 | 23.88 | 164.62 | 0.48 | 3.31 | 0.36 | 2.45 |
| S20x12-L20-P27 | 23.92 | 164.93 | 23.80 | 164.13 | 0.43 | 2.94 | 0.32 | 2.19 |
| S20x12-L20-P29 | 23.93 | 164.99 | 23.67 | 163.18 | 0.41 | 2.86 | 0.35 | 2.41 |
| S20x12-L16-P25 | 20.94 | 144.35 | 20.85 | 143.78 | 0.36 | 2.48 | 0.28 | 1.92 |
| S20x12-L16-P27 | 21.05 | 145.12 | 20.80 | 143.44 | 0.31 | 2.13 | 0.27 | 1.85 |
| S20x12-L16-P29 | 21.04 | 145.07 | 20.69 | 142.63 | 0.28 | 1.91 | 0.26 | 1.78 |
| S20x12-L12-P25 | 18.03 | 124.30 | 17.84 | 123.02 | 0.28 | 1.96 | 0.22 | 1.52 |
| S20x12-L12-P27 | 18.13 | 125.03 | 17.83 | 122.97 | 0.25 | 1.73 | 0.21 | 1.43 |
| S20x12-L12-P29 | 17.96 | 123.87 | 17.75 | 122.36 | 0.22 | 1.55 | 0.19 | 1.33 |
| S16x9-L20-P25 | 21.54 | 148.52 | 21.32 | 147.00 | 0.42 | 2.87 | 0.20 | 1.39 |
| S16x9-L20-P27 | 21.56 | 148.68 | 21.27 | 146.63 | 0.36 | 2.47 | 0.16 | 1.11 |
| S16x9-L20-P29 | 21.51 | 148.34 | 21.17 | 145.96 | 0.30 | 2.05 | 0.14 | 1.00 |
| S16x9-L16-P25 | 18.49 | 127.50 | 18.26 | 125.88 | 0.34 | 2.34 | 0.16 | 1.11 |
| S16x9-L16-P27 | 18.54 | 127.86 | 18.30 | 126.20 | 0.28 | 1.92 | 0.13 | 0.92 |
| S16x9-L16-P29 | 18.57 | 128.07 | 18.37 | 126.63 | 0.24 | 1.64 | 0.11 | 0.77 |
| S16x9-L12-P25 | 15.63 | 107.74 | 15.23 | 105.02 | 0.25 | 1.72 | 0.11 | 0.79 |
| S16x9-L12-P27 | 15.48 | 106.74 | 15.39 | 106.08 | 0.21 | 1.44 | 0.10 | 0.66 |
| S16x9-L12-P29 | 15.61 | 107.62 | 15.51 | 106.93 | 0.20 | 1.38 | 0.10 | 0.68 |
| S12x6-L20-P25 | 9.77 | 67.34 | 9.79 | 67.53 | 0.07 | 0.47 | 0.05 | 0.37 |
| S12x6-L20-P27 | 9.73 | 67.06 | 9.86 | 68.01 | 0.07 | 0.46 | 0.05 | 0.33 |
| S12x6-L20-P29 | 9.72 | 67.03 | 9.89 | 68.19 | 0.05 | 0.36 | 0.04 | 0.30 |
| S12x6-L16-P25 | 8.51 | 58.71 | 8.51 | 58.69 | 0.06 | 0.42 | 0.05 | 0.32 |
| S12x6-L16-P27 | 8.47 | 58.38 | 8.41 | 57.97 | 0.05 | 0.37 | 0.04 | 0.27 |
| S12x6-L16-P29 | 8.37 | 57.70 | 8.36 | 57.63 | 0.05 | 0.33 | 0.04 | 0.25 |
| S12x6-L12-P25 | 7.09 | 48.88 | 7.09 | 48.90 | 0.05 | 0.31 | 0.04 | 0.26 |
| S12x6-L12-P27 | 7.05 | 48.64 | 7.00 | 48.24 | 0.04 | 0.29 | 0.03 | 0.23 |
| S12x6-L12-P29 | 6.95 | 47.94 | 6.91 | 47.61 | 0.04 | 0.24 | 0.03 | 0.20 |

Table A3.2.4 – Pole Stresses at V=61.2 mph (27.4 m/s)

| Model | S21 | | | |
|----------------|------------|--------|-------------|--------|
| | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 14.13 | 97.43 | 13.79 | 95.11 |
| S20x12-L20-P27 | 15.22 | 104.91 | 15.17 | 104.59 |
| S20x12-L20-P29 | 16.41 | 113.14 | 16.75 | 115.48 |
| S20x12-L16-P25 | 13.96 | 96.26 | 13.50 | 93.06 |
| S20x12-L16-P27 | 14.43 | 99.46 | 14.84 | 102.31 |
| S20x12-L16-P29 | 16.16 | 111.42 | 16.43 | 113.32 |
| S20x12-L12-P25 | 14.08 | 97.08 | 13.55 | 93.40 |
| S20x12-L12-P27 | 14.96 | 103.13 | 15.06 | 103.81 |
| S20x12-L12-P29 | 16.93 | 116.72 | 16.52 | 113.87 |
| S16x9-L20-P25 | 8.04 | 55.41 | 8.17 | 56.35 |
| S16x9-L20-P27 | 8.85 | 61.04 | 9.16 | 63.15 |
| S16x9-L20-P29 | 9.81 | 67.62 | 10.03 | 69.16 |
| S16x9-L16-P25 | 7.90 | 54.49 | 8.16 | 56.25 |
| S16x9-L16-P27 | 8.76 | 60.40 | 9.10 | 62.78 |
| S16x9-L16-P29 | 9.75 | 67.24 | 9.88 | 68.15 |
| S16x9-L12-P25 | 8.01 | 55.25 | 8.04 | 55.47 |
| S16x9-L12-P27 | 8.76 | 60.39 | 8.90 | 61.36 |
| S16x9-L12-P29 | 9.70 | 66.90 | 9.71 | 66.93 |
| S12x6-L20-P25 | 5.55 | 38.27 | 5.84 | 40.24 |
| S12x6-L20-P27 | 6.24 | 43.00 | 6.42 | 44.29 |
| S12x6-L20-P29 | 6.76 | 46.61 | 7.09 | 48.90 |
| S12x6-L16-P25 | 5.54 | 38.22 | 5.65 | 38.96 |
| S12x6-L16-P27 | 6.18 | 42.58 | 6.25 | 43.11 |
| S12x6-L16-P29 | 6.69 | 46.12 | 6.59 | 45.41 |
| S12x6-L12-P25 | 5.49 | 37.83 | 5.52 | 38.03 |
| S12x6-L12-P27 | 5.97 | 41.15 | 6.01 | 41.46 |
| S12x6-L12-P29 | 6.46 | 44.52 | 6.59 | 45.45 |

Table A3.3.1 – Displacements at V=105mph (46.9 m/s)

| Model | ΔUZ | | | | ΔUY | | | |
|----------------|-------------|---------|-------------|---------|-------------|-------|-------------|-------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | in. | mm | in. | mm | in. | mm | in. | mm |
| S20x12-L20-P25 | 66.38 | 1686.08 | 64.51 | 1638.60 | 0.92 | 23.24 | 1.24 | 31.51 |
| S20x12-L20-P27 | 70.87 | 1800.10 | 68.72 | 1745.60 | 0.94 | 23.82 | 1.14 | 29.08 |
| S20x12-L20-P29 | 75.66 | 1921.82 | 73.27 | 1861.07 | 0.90 | 22.83 | 1.03 | 26.27 |
| S20x12-L16-P25 | 49.78 | 1264.44 | 48.31 | 1227.16 | 0.82 | 20.79 | 1.12 | 28.47 |
| S20x12-L16-P27 | 53.62 | 1362.03 | 52.04 | 1321.78 | 0.78 | 19.75 | 1.09 | 27.57 |
| S20x12-L16-P29 | 57.76 | 1467.14 | 55.95 | 1421.13 | 0.79 | 20.04 | 1.00 | 25.46 |
| S20x12-L12-P25 | 35.01 | 889.21 | 34.58 | 878.43 | 0.60 | 15.21 | 0.80 | 20.32 |
| S20x12-L12-P27 | 38.28 | 972.20 | 37.76 | 959.16 | 0.60 | 15.29 | 0.85 | 21.67 |
| S20x12-L12-P29 | 41.85 | 1062.90 | 40.92 | 1039.27 | 0.61 | 15.37 | 0.87 | 22.20 |
| S16x9-L20-P25 | 42.93 | 1090.54 | 42.46 | 1078.49 | 0.47 | 11.83 | 0.42 | 10.56 |
| S16x9-L20-P27 | 45.56 | 1157.32 | 45.12 | 1146.16 | 0.48 | 12.23 | 0.45 | 11.40 |
| S16x9-L20-P29 | 47.75 | 1212.79 | 47.70 | 1211.65 | 0.52 | 13.17 | 0.48 | 12.14 |
| S16x9-L16-P25 | 31.09 | 789.59 | 30.70 | 779.73 | 0.44 | 11.10 | 0.31 | 7.75 |
| S16x9-L16-P27 | 33.31 | 846.15 | 32.86 | 834.56 | 0.39 | 9.96 | 0.27 | 6.89 |
| S16x9-L16-P29 | 35.85 | 910.71 | 35.13 | 892.27 | 0.38 | 9.70 | 0.30 | 7.74 |
| S16x9-L12-P25 | 21.26 | 539.89 | 21.18 | 537.89 | 0.31 | 7.76 | 0.36 | 9.11 |
| S16x9-L12-P27 | 23.29 | 591.44 | 22.93 | 582.43 | 0.32 | 8.18 | 0.31 | 7.91 |
| S16x9-L12-P29 | 25.25 | 641.31 | 24.85 | 631.13 | 0.34 | 8.62 | 0.27 | 6.97 |
| S12x6-L20-P25 | 23.36 | 593.40 | 23.93 | 607.89 | 0.21 | 5.42 | 0.21 | 5.35 |
| S12x6-L20-P27 | 24.87 | 631.64 | 25.39 | 645.02 | 0.24 | 6.22 | 0.22 | 5.66 |
| S12x6-L20-P29 | 26.40 | 670.62 | 26.75 | 679.52 | 0.26 | 6.69 | 0.24 | 5.98 |
| S12x6-L16-P25 | 17.36 | 441.01 | 17.96 | 456.22 | 0.19 | 4.80 | 0.20 | 5.16 |
| S12x6-L16-P27 | 18.68 | 474.35 | 19.15 | 486.38 | 0.20 | 5.02 | 0.18 | 4.64 |
| S12x6-L16-P29 | 19.96 | 506.86 | 20.67 | 524.97 | 0.22 | 5.51 | 0.20 | 4.97 |
| S12x6-L12-P25 | 12.18 | 309.27 | 12.61 | 320.30 | 0.15 | 3.74 | 0.13 | 3.33 |
| S12x6-L12-P27 | 13.37 | 339.55 | 13.91 | 353.20 | 0.15 | 3.88 | 0.14 | 3.52 |
| S12x6-L12-P29 | 14.67 | 372.57 | 15.07 | 382.66 | 0.18 | 4.49 | 0.15 | 3.69 |

Table A3.3.2 – Top Box-Connection Stresses at V=105mph (46.9 m/s)

| Model | S33 | | | | S11 | | | |
|----------------|------------|--------|-------------|--------|------------|------|-------------|------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 48.76 | 336.22 | 48.78 | 336.35 | 0.73 | 5.03 | 0.57 | 3.95 |
| S20x12-L20-P27 | 48.77 | 336.30 | 48.93 | 337.40 | 0.60 | 4.16 | 0.51 | 3.51 |
| S20x12-L20-P29 | 48.66 | 335.53 | 49.18 | 339.12 | 0.51 | 3.51 | 0.44 | 3.06 |
| S20x12-L16-P25 | 42.33 | 291.85 | 42.03 | 289.80 | 0.52 | 3.56 | 0.53 | 3.63 |
| S20x12-L16-P27 | 42.32 | 291.78 | 42.15 | 290.62 | 0.43 | 2.95 | 0.47 | 3.23 |
| S20x12-L16-P29 | 42.15 | 290.60 | 42.17 | 290.75 | 0.39 | 2.68 | 0.42 | 2.87 |
| S20x12-L12-P25 | 35.59 | 245.36 | 35.49 | 244.71 | 0.36 | 2.47 | 0.42 | 2.86 |
| S20x12-L12-P27 | 35.61 | 245.51 | 35.26 | 243.10 | 0.36 | 2.48 | 0.45 | 3.09 |
| S20x12-L12-P29 | 35.40 | 244.10 | 35.48 | 244.60 | 0.32 | 2.20 | 0.41 | 2.84 |
| S16x9-L20-P25 | 50.20 | 346.14 | 50.09 | 345.36 | 0.48 | 3.30 | 0.35 | 2.38 |
| S16x9-L20-P27 | 50.05 | 345.13 | 49.73 | 342.89 | 0.35 | 2.39 | 0.26 | 1.77 |
| S16x9-L20-P29 | 49.99 | 344.70 | 49.58 | 341.88 | 0.30 | 2.05 | 0.22 | 1.48 |
| S16x9-L16-P25 | 43.44 | 299.53 | 43.40 | 299.24 | 0.34 | 2.33 | 0.22 | 1.55 |
| S16x9-L16-P27 | 36.00 | 248.22 | 36.00 | 248.22 | 0.30 | 2.10 | 0.20 | 1.37 |
| S16x9-L16-P29 | 43.25 | 298.23 | 42.77 | 294.88 | 0.23 | 1.61 | 0.16 | 1.09 |
| S16x9-L12-P25 | 36.29 | 250.25 | 36.35 | 250.67 | 0.20 | 1.39 | 0.16 | 1.10 |
| S16x9-L12-P27 | 36.27 | 250.08 | 36.13 | 249.13 | 0.18 | 1.22 | 0.14 | 0.93 |
| S16x9-L12-P29 | 36.17 | 249.36 | 35.80 | 246.84 | 0.16 | 1.13 | 0.12 | 0.81 |
| S12x6-L20-P25 | 23.36 | 161.09 | 23.56 | 162.46 | 0.11 | 0.72 | 0.08 | 0.52 |
| S12x6-L20-P27 | 23.28 | 160.54 | 23.43 | 161.54 | 0.10 | 0.66 | 0.07 | 0.50 |
| S12x6-L20-P29 | 23.24 | 160.24 | 23.30 | 160.63 | 0.09 | 0.60 | 0.07 | 0.52 |
| S12x6-L16-P25 | 19.57 | 134.96 | 20.07 | 138.35 | 0.09 | 0.64 | 0.07 | 0.48 |
| S12x6-L16-P27 | 19.72 | 135.95 | 20.20 | 139.29 | 0.08 | 0.58 | 0.06 | 0.43 |
| S12x6-L16-P29 | 19.85 | 136.89 | 20.22 | 139.43 | 0.08 | 0.53 | 0.06 | 0.39 |
| S12x6-L12-P25 | 16.20 | 111.71 | 16.62 | 114.63 | 0.07 | 0.47 | 0.04 | 0.26 |
| S12x6-L12-P27 | 16.26 | 112.08 | 16.60 | 114.46 | 0.07 | 0.45 | 0.04 | 0.26 |
| S12x6-L12-P29 | 16.34 | 112.65 | 16.60 | 114.43 | 0.06 | 0.44 | 0.04 | 0.27 |


Table A3.3.3 – Bottom Box-Connection Stresses at V=105mph (46.9 m/s)

| Model | S33 | | | | S11 | | | |
|----------------|------------|--------|-------------|--------|------------|------|-------------|------|
| | w/ Walkway | | w/o Walkway | | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 70.61 | 486.85 | 69.99 | 482.56 | 1.21 | 8.32 | 0.99 | 6.84 |
| S20x12-L20-P27 | 70.92 | 488.96 | 69.81 | 481.37 | 1.03 | 7.13 | 0.86 | 5.96 |
| S20x12-L20-P29 | 71.03 | 489.76 | 69.48 | 479.05 | 0.84 | 5.81 | 0.73 | 5.06 |
| S20x12-L16-P25 | 62.08 | 428.03 | 61.22 | 422.12 | 0.91 | 6.26 | 0.90 | 6.18 |
| S20x12-L16-P27 | 62.39 | 430.17 | 61.05 | 420.91 | 0.77 | 5.32 | 0.81 | 5.59 |
| S20x12-L16-P29 | 62.38 | 430.12 | 61.08 | 421.13 | 0.71 | 4.90 | 0.71 | 4.91 |
| S20x12-L12-P25 | 53.61 | 369.62 | 52.48 | 361.82 | 0.68 | 4.67 | 0.79 | 5.47 |
| S20x12-L12-P27 | 53.40 | 368.19 | 52.29 | 360.55 | 0.66 | 4.53 | 0.82 | 5.64 |
| S20x12-L12-P29 | 53.20 | 366.81 | 52.16 | 359.63 | 0.58 | 3.99 | 0.76 | 5.27 |
| S16x9-L20-P25 | 62.43 | 430.46 | 61.73 | 425.64 | 0.80 | 5.50 | 0.60 | 4.12 |
| S16x9-L20-P27 | 62.03 | 427.73 | 61.60 | 424.72 | 0.64 | 4.42 | 0.44 | 3.02 |
| S16x9-L20-P29 | 62.45 | 430.57 | 61.36 | 423.11 | 0.51 | 3.49 | 0.38 | 2.59 |
| S16x9-L16-P25 | 53.54 | 369.18 | 52.84 | 364.31 | 0.64 | 4.44 | 0.44 | 3.02 |
| S16x9-L16-P27 | 36.00 | 248.23 | 36.00 | 248.22 | 0.79 | 5.43 | 0.51 | 3.53 |
| S16x9-L16-P29 | 53.78 | 370.82 | 53.19 | 366.74 | 0.39 | 2.67 | 0.29 | 2.02 |
| S16x9-L12-P25 | 44.71 | 308.30 | 44.11 | 304.15 | 0.42 | 2.87 | 0.32 | 2.18 |
| S16x9-L12-P27 | 44.84 | 309.14 | 44.59 | 307.46 | 0.35 | 2.40 | 0.25 | 1.76 |
| S16x9-L12-P29 | 45.23 | 311.89 | 44.99 | 310.21 | 0.33 | 2.25 | 0.22 | 1.52 |
| S12x6-L20-P25 | 28.09 | 193.71 | 28.03 | 193.27 | 0.19 | 1.29 | 0.15 | 1.00 |
| S12x6-L20-P27 | 27.81 | 191.75 | 28.09 | 193.71 | 0.19 | 1.30 | 0.15 | 1.02 |
| S12x6-L20-P29 | 27.74 | 191.28 | 28.34 | 195.43 | 0.17 | 1.16 | 0.14 | 0.94 |
| S12x6-L16-P25 | 24.43 | 168.47 | 24.49 | 168.88 | 0.19 | 1.28 | 0.13 | 0.93 |
| S12x6-L16-P27 | 24.35 | 167.87 | 24.24 | 167.13 | 0.17 | 1.15 | 0.12 | 0.82 |
| S12x6-L16-P29 | 24.12 | 166.29 | 23.99 | 165.44 | 0.16 | 1.11 | 0.12 | 0.80 |
| S12x6-L12-P25 | 20.34 | 140.27 | 20.44 | 140.95 | 0.13 | 0.87 | 0.09 | 0.64 |
| S12x6-L12-P27 | 20.29 | 139.88 | 20.47 | 141.16 | 0.11 | 0.78 | 0.09 | 0.60 |
| S12x6-L12-P29 | 20.06 | 138.30 | 19.82 | 136.64 | 0.12 | 0.81 | 0.09 | 0.61 |

Table A3.3.4 – Pole Stresses at V=105mph (46.9 m/s)


| Model | S21 | | | |
|----------------|------------|--------|-------------|--------|
| | w/ Walkway | | w/o Walkway | |
| | ksi | MPa | ksi | MPa |
| S20x12-L20-P25 | 42.24 | 291.24 | 40.47 | 279.05 |
| S20x12-L20-P27 | 45.85 | 316.17 | 44.47 | 306.64 |
| S20x12-L20-P29 | 48.74 | 336.03 | 49.12 | 338.65 |
| S20x12-L16-P25 | 40.50 | 279.28 | 39.14 | 269.87 |
| S20x12-L16-P27 | 42.52 | 293.19 | 43.40 | 299.25 |
| S20x12-L16-P29 | 47.99 | 330.92 | 48.18 | 332.22 |
| S20x12-L12-P25 | 40.46 | 278.97 | 39.20 | 270.27 |
| S20x12-L12-P27 | 43.49 | 299.84 | 44.32 | 305.56 |
| S20x12-L12-P29 | 49.10 | 338.51 | 48.56 | 334.84 |
| S16x9-L20-P25 | 23.29 | 160.58 | 23.68 | 163.24 |
| S16x9-L20-P27 | 26.77 | 184.60 | 26.60 | 183.38 |
| S16x9-L20-P29 | 28.46 | 196.25 | 29.18 | 201.20 |
| S16x9-L16-P25 | 22.94 | 158.18 | 23.63 | 162.90 |
| S16x9-L16-P27 | 25.83 | 178.08 | 26.35 | 181.71 |
| S16x9-L16-P29 | 28.26 | 194.84 | 28.93 | 199.46 |
| S16x9-L12-P25 | 23.24 | 160.22 | 23.27 | 160.46 |
| S16x9-L12-P27 | 25.42 | 175.26 | 25.69 | 177.11 |
| S16x9-L12-P29 | 28.13 | 193.94 | 27.98 | 192.93 |
| S12x6-L20-P25 | 16.03 | 110.51 | 16.91 | 116.56 |
| S12x6-L20-P27 | 18.01 | 124.16 | 18.59 | 128.18 |
| S12x6-L20-P29 | 19.52 | 134.62 | 19.85 | 136.89 |
| S12x6-L16-P25 | 16.11 | 111.04 | 16.94 | 116.79 |
| S12x6-L16-P27 | 17.89 | 123.36 | 18.96 | 130.74 |
| S12x6-L16-P29 | 19.67 | 135.60 | 19.35 | 133.43 |
| S12x6-L12-P25 | 16.00 | 110.30 | 16.43 | 113.26 |
| S12x6-L12-P27 | 17.05 | 117.57 | 17.29 | 119.24 |
| S12x6-L12-P29 | 18.51 | 127.65 | 19.96 | 137.60 |

Appendix B



1 FRONT OF SIGN
1" = 1'-0" (2.54 cm)


② BACK OF SIGN
1" = 1'-0" (2.54 cm)



3 SIDE SIGN
1" = 1'-0" (2.)

4 SIGN HANGING
1" = 1'-0" (2.54 cm)


⑤ GRATE
1" = 1'-0"



③ SIDE SIGN
1" = 1'-0" (2.54 cm = 30.48 cm)

SIGN HANGING
1" = 1'-0" (2.54 cm = 30.48 cm)





GRATE
1" = 1'-0" (2.54 cm = 30.48 cm)

[illegible]

| | |
|-------------------|---------|
| MODEL SIGN | |
| Project number | |
| Date | 5-21-18 |
| Drawn by | HS |
| Checked by | |
| S - 1.0 | |
| Scale 1" = 1'-0" | |

| STATE | PROJECT NO. | YEAR | SHEET NO. | TOTAL SHEETS |
|--------|-------------|------|-----------|--------------|
| KANSAS | | | | |


Note: The net area of the handhole frame bar shall be maintained at the handhole. The net area of the pole section shall be maintained at the handhole. The net area of the pole section shall be maintained at the handhole.



* Note: See next sheet for details A, B, C & D.

Note: See "Construction Layout" sheet for "X", "W", "C", "Arm Length" and "Design No."

| Dimension Design | Pole Dimension | Arm Dimension | A | T1 | S | F | B.C. | W1 | W2 | P | Anchor Bolt Size | T2 | T3 | G | E | H | J | Bolt Size | W3 | W4 |
|------------------|--------------------------|---------------------------|-------|--------|-----------|-----------|-----------|------|-------|-------|------------------|--------|--------|---------|-----------|-----------|--------|-----------------|------|------|
| 1 | 16.0" O.D. x 0.375" Wall | 8.625" O.D. x 0.500" Wall | 4'-0" | 2' | 1'-11" | 1'-3 1/2" | 1'-10" | 3/8" | 3/8" | 7/8" | 2" x 4"-8" | 1 5/8" | 7/8" | 10" | 1'-11" | 1'-5 1/2" | 7 1/4" | 7/8" x 3 3/4" | 3/8" | 1/2" |
| 2 | 18.0" O.D. x 0.375" Wall | 10.75" O.D. x 0.307" Wall | 6'-0" | 2 1/2" | 2'-2 1/2" | 1'-6" | 2'-1 1/2" | 3/8" | 3/8" | 7/8" | 2" x 4"-8" | 1 5/8" | 7/8" | 10 3/4" | 2'-0 1/2" | 1'-5 1/2" | 7 1/2" | 7/8" x 3 3/4" | 3/8" | 5/8" |
| 3 | 18.0" O.D. x 0.375" Wall | 12.75" O.D. x 0.250" Wall | 6'-0" | 2 1/2" | 2'-2 1/2" | 1'-6" | 2'-1 1/2" | 3/8" | 3/8" | 7/8" | 2" x 4"-8" | 1 5/8" | 7/8" | 10 3/4" | 2'-0 1/2" | 1'-5 1/2" | 8 5/8" | 7/8" x 3 3/4" | 1/4" | 1/4" |
| 4 | 18.0" O.D. x 0.500" Wall | 12.75" O.D. x 0.250" Wall | 6'-0" | 2 1/2" | 2'-2 1/2" | 1'-6" | 2'-1 1/2" | 1/2" | 7/16" | 9/16" | 2 1/4" x 5"-3" | 1 1/2" | 7/8" | 10 3/4" | 2'-0 1/2" | 1'-5 1/2" | 8 5/8" | 7/8" x 3 3/4" | 1/4" | 1/4" |
| 5 | 18.0" O.D. x 0.375" Wall | 12.75" O.D. x 0.375" Wall | 6'-0" | 2 1/2" | 2'-2 1/2" | 1'-6" | 2'-1 1/2" | 1/2" | 7/16" | 9/16" | 2 1/4" x 5"-3" | 1 1/2" | 1" | 11" | 2'-1 1/2" | 1'-8 1/4" | 8 5/8" | 1" x 4 1/4" | 3/8" | 3/8" |
| 6 | 18.0" O.D. x 0.500" Wall | 12.75" O.D. x 0.500" Wall | 6'-0" | 2 1/2" | 2'-2 1/2" | 1'-6" | 2'-1 1/2" | 1/2" | 7/16" | 9/16" | 2 1/4" x 5"-3" | 2" | 1 1/8" | 11 1/8" | 2'-2 1/4" | 1'-9 1/2" | 8 5/8" | 1 1/8" x 4 1/2" | 3/8" | 1/2" |





CAMBER DIAGRAM


| NO. | DATE | REVISIONS | BY | APPD |
|-----|------|-----------|----|------|
| 3 | | | | |

KANSAS DEPARTMENT OF TRANSPORTATION
STANDARD STRUCTURAL SIGN SUPPORTS
CANTILEVER TYPE OVERHEAD
SUPPORT DETAILS
UNIFORM TUBE ALTERNATE
SUSPENSION
DESIGNED BY: J. L. BROWN
CHECKED BY: J. L. BROWN
APPROVED BY: J. L. BROWN
THIRD CLASS


| STATE | PROJECT NO. | YEAR | SHEET NO. | TOTAL SHEETS |
|--------|-------------|------|-----------|--------------|
| KANSAS | | | | |




Elevation & Section




Plan




Section B-B



Section C-C




Elevation



Section A-A

| Design No. | R |
|------------|--------|
| 1 | 36.875 |
| 2 | 58.75 |
| 3 thru 6 | 56.75 |

DETAIL D



DETAIL A

DETAIL B

| NO. | DATE | REVISIONS | BY | APPROVED |
|-----|------|-----------|----|----------|
| | | | | |

KANSAS DEPARTMENT OF TRANSPORTATION
STANDARD STRUCTURAL SIGN SUPPORTS
CANTILEVER TYPE OVERHEAD
STEEL SUPPORT DETAILS
SUS2C-02
UNIFORM TUBE ALTERNATE

DESIGNER: J. L. BROWN
CHECKER: J. L. BROWN
APPROVED: J. L. BROWN
DATE: 10/1/00

Plot Date: 10-JUL-2006 09:44
Plot Location: Bridge Design
Plotted By: mper
File: W:\000\11\Department\Designing and Lightings & L Standards - SUS2C-02.dgn
Std Base File: SUS2C-02.dgn

